



METROPOLITAN GOVERNMENT OF NASHVILLE AND DAVIDSON COUNTY

Metropolitan Historic Zoning Commission
Sunnyside in Sevier Park
3000 Granny White Pike
Nashville, Tennessee 37204
Telephone: (615) 862-7970
Fax: (615) 862-7974

STAFF RECOMMENDATION

1411 Ordway Place

November 20, 2013

Application: Demolition; New construction- infill and outbuilding

District: Lockeland Springs-East End Neighborhood Conservation Zoning Overlay

Council District: 06

Map and Parcel Number: 08309028900

Applicant: Robert Thompson, Architect

Project Lead: Sean Alexander, sean.alexander@nashville.gov

Description of Project: The applicant is proposing to demolish a non-contributing structure and replace it with a new house with a detached accessory building. The house will be two stories tall with a “Gabled-L” form. The exterior of the structure will be clad with cement-fiber siding with wood trim. The roof will be composition shingles and the foundation will be split-faced concrete block. The garage will be two stories tall, with height and massing subordinate to the primary building. The materials of the garage will match those of the house.

Recommendation Summary: Staff recommends approval of the application with the conditions that:

- Staff approve the color of the roof and the materials of the windows and doors;
- A walkway be added from the front porch to the street, and that the location of HVAC units and utilities be approved by Staff,

Meeting those conditions, staff finds that the proposal meets the design guidelines for the Lockeland Springs-East End Neighborhood Conservation Zoning Overlay.

Attachments

A: Photographs


B: Site Plan

C: Elevations

Vicinity Map:



Aerial Map:



Applicable Design Guidelines:

II.B. New Construction

1. Height

New buildings must be constructed to the same number of stories and to a height which is compatible with the height of adjacent buildings.

The height of the foundation wall, porch roof, and main roofs should all be compatible with those of surrounding historic buildings.

2. Scale

The size of a new building and its mass in relation to open spaces; and its windows, doors, openings, and porches should be visually compatible with surrounding historic buildings.

Foundation lines should be visually distinct from the predominant exterior wall material. This is typically accomplished with a change in material.

3. Setback and Rhythm of Spacing

The setback from front and side yard property lines established by adjacent historic buildings must be maintained. When a definite rhythm along a street is established by uniform lot and building width, infill new buildings should maintain that rhythm.

4. Relationship of Materials, Textures, Details, and Material Colors

The relationship and use of materials, textures, details, and material color of a new building's public facades shall be visually compatible with and similar to those of adjacent buildings, or shall not contrast conspicuously.

T-1-11- type building panels, "permastone", E.F.I.S. and other artificial siding materials are generally not appropriate. However, pre-cast stone and cement fiberboard siding are approvable cladding materials for new construction; but pre-cast stone should be of a compatible color and texture to existing historic stone clad structures in the district; and cement fiberboard siding, when used for lapped siding, should be smooth and not stamped or embossed and have a maximum of a 5" reveal.

Shingle siding should exhibit a straight-line course pattern and exhibit a maximum exposure of seven inches (7").

Four inch (4") nominal corner boards are required at the face of each exposed corner.

Stud wall lumber and embossed wood grain are prohibited.

Belt courses or a change in materials from one story to another are often encouraged for large two-story buildings to break up the massing.

When different materials are used, it is most appropriate to have the change happen at floor lines.

Clapboard sided chimneys are generally not appropriate. Masonry or stucco is appropriate.

Texture and tooling of mortar on new construction should be similar to historic examples.

Asphalt shingle is an appropriate roof material for most buildings. Generally, roofing should not have strong simulated shadows in the granule colors which results in a rough, pitted appearance; faux shadow lines; strongly variegated colors; colors that are too light (e.g.: tan, white, light green); wavy or deep color/texture used to simulate split shake shingles or slate; excessive flared form in the shingle tabs; uneven or sculpted bottom edges that emphasize tab width or edges, unless matching the original roof.

5. Roof Shape

The roofs of new buildings shall be visually compatible, by not contrasting greatly, with the roof shape and orientation of surrounding buildings.

Roof pitches should be similar to the pitches found in the district. Historic roofs are generally between 6/12 and 12/12.

Roof pitches for porch roofs are typically less steep, approximately in the 3-4/12 range.

Generally, two-story residential buildings have hipped roofs.

Generally, dormers should be located on the roof. Wall dormers are not typical in the historic context and accentuate height so they should be used minimally and generally only on secondary facades. When they are appropriate they should be no wider than the typical window openings and should not project beyond the main wall.

6. Orientation

The site orientation of new buildings shall be consistent with that of adjacent buildings and shall be visually compatible. Directional expression shall be compatible with surrounding buildings, whether that expression is vertical, horizontal, or non-directional.

New buildings should incorporate at least one front street-related porch that is accessible from the front street.

Side porches or porte cocheres may also be appropriate as a secondary entrance, but the primary entrance should address the front.

Front porches generally should be a minimum of 6' deep, have porch racks that are 1'-3' tall and have posts that include bases and capitals.

Generally, curb cuts should not be added.

Where a new driveway is appropriate it should be two concrete strips with a central grassy median.

Shared driveways should be a single lane, not just two driveways next to each other. Sometimes this may be accomplished with a single lane curb cut that widens to a double lane deeper into the lot.

7. Proportion and Rhythm of Openings

The relationship of width to height of windows and doors, and the rhythm of solids (walls) to voids (door and window openings) in a new building shall be compatible, by not contrasting greatly, with surrounding historic buildings.

Window openings on the primary street-related or front façade of new construction should be representative of the window patterns of similarly massed historic structures within the district.

In most cases, every 8-13 horizontal feet of flat wall surface should have an opening (window or door) of at least 4 square feet. More leniencies can be given to minimally visible side or rear walls.

Double-hung windows should exhibit a height to width ratio of at least 2:1.

Windows on upper floors should not be taller than windows on the main floor since historically first floors have higher ceilings than upper floors and so windows were typically taller on the first floor.

Single-light sashes are appropriate for new construction. If using multi-light sashes, muntins should be fully simulated and bonded to the glass, and exhibit an interior bar, exterior bar, as well as a spacer between glass panes.

Four inch (nominal) casings are required around doors, windows and vents on non-masonry buildings. Trim should be thick enough to extend beyond the clapboard. Double or triple windows should have a 4" to 6" mullion in between.

Brick molding is required around doors, windows and vents within masonry walls but is not appropriate on non-masonry buildings.

8. Outbuildings

- a. Garages and storage buildings should reflect the character of the existing house and surrounding buildings and should be compatible in terms of height, scale, roof shape, materials, texture, and details.

Historically, outbuildings were either very utilitarian in character, or (particularly with more extravagant houses) they repeated the roof forms and architectural details of the houses to which they related.

Generally, either approach is appropriate for new outbuildings.

Outbuildings: Roof

Generally, the eaves and roof ridge of any new accessory structure should not be higher than those of the existing house.

Roof slopes on simple, utilitarian buildings do not have to match the roof slopes of the main structure, but must maintain at least a 4/12 pitch.

The front face of any street-facing dormer should sit back at least 2' from the wall of the floor below.

Outbuildings: Windows and Doors

Publicly visible windows should be appropriate to the style of the house.

Double-hung windows are generally twice as tall as they are wide and of the single-light sash variety.

Publicly visible pedestrian doors must either be appropriate for the style of house to which the outbuilding relates or be flat with no panels.

Metal overhead doors are acceptable on garages when they are simple and devoid of overly decorative elements typical on high-style wooden doors.

For street-facing facades, garages with more than one-bay should have multiple single doors rather than one large door to accommodate more than one bay.

Decorative raised panels on publicly visible garage doors are generally not appropriate.

Outbuildings: Siding and Trim

Brick, weatherboard, and board-and-batten are typical siding materials. Outbuildings with weatherboard siding typically have wide cornerboards and window and door casings (trim).

Exterior siding may match the existing contributing building's original siding; otherwise, siding should be wood or smooth cement-fiberboard lap siding with a maximum exposure of five inches (5"), wood or smooth cement-fiberboard board-and-batten or masonry.

Four inch (4" nominal) corner-boards are required at the face of each exposed corner.

Stud wall lumber and embossed wood grain are prohibited.

Four inch (4" nominal) casings are required around doors, windows, and vents within clapboard walls.

Trim should be thick enough to extend beyond the clapboard. Double or triple windows should have a 4" to 6" mullion in between.

Brick molding is required around doors, windows, and vents within masonry walls but is not appropriate on non-masonry clad buildings.

- b. Garages, if visible from the street, should be situated on the lot as historically traditional for the neighborhood.

Generally new garages should be placed close to the alley, at the rear of the lot, or in the original location of an historic accessory structure.

Lots without rear alleys may have garages located closer to the primary structure. The appropriate location is one that matches the neighborhood or can be documented by historic maps.

Generally, attached garages are not appropriate; however, instances where they may be are:

· Where they are a typical feature of the neighborhood; or

When the location of the attached garage is in the general location of an historic accessory building, the new garage is located in the basement level, and the vehicular access is on the rear elevation.

- c. The location and design of outbuildings should not be visually disruptive to the character of the surrounding buildings.

9. Appurtenances

Appurtenances related to new buildings, including driveways, sidewalks, lighting, fences, and walls, shall be visually compatible with the environment of the existing buildings and sites to which they relate.

Utilities

Utility connections such as gas meters, electric meters, phone, cable, and HVAC condenser units should be located so as to minimize their visibility from the street.

Generally, utility connections should be placed no closer to the street than the mid point of the structure. Power lines should be placed underground if they are carried from the street and not from the rear or an alley.

IV. B. Demolition

Demolition is not appropriate

- a. if a building, or major portion of a building, is of such architectural or historical interest and value that its removal would be detrimental to the public interest; or
- b. if a building, or major portion of a building, is of such old or unusual or uncommon design and materials that it could not be reproduced or be reproduced without great difficulty and expense.

Demolition is appropriate

- a. if a building, or major portion of a building, has irretrievably lost its architectural and historical integrity and significance and its removal will result in a more historically appropriate visual effect on the district;
- b. if a building, or major portion of a building, does not contribute to the historical and architectural character and significance of the district and its removal will result in a more historically appropriate visual effect on the district; or
- c. if the denial of the demolition will result in an economic hardship on the applicant as determined by the MHZC in accordance with section 17.40.420 (Historic Zoning Regulations), Metropolitan Comprehensive Zoning Ordinance.

Background: There is a one-story brick house at 1411 Ordway Place that was constructed circa 1965.

Analysis and Findings:

The applicant is proposing to demolish the existing structure and to construct a new house and a detached outbuilding.



Demolition:

Because its date of construction is well after the significant period of development for the neighborhood, it does not contribute to the historic character of the district.

The proposal to demolish the non-contributing house meets section III.B.2 for appropriate demolition and does not meet section III.B.1 for inappropriate demolition.

Height & Scale:

The new house will be two-stories tall with a “Gabled-L” form. The front-facing gable will have a ridge height of twenty-nine feet, six inches (29’-6”) above grade and eaves at twenty-feet (20’). The side gable will have a ridge height of twenty-five feet, six inches (25’-6”) and eaves at seventeen feet (17’) above grade. The finished floor level of the building will be approximately two feet (2’) above grade, with two courses of foundation block and a wood water-table band.

The house will be thirty-six feet (36’) wide overall, although the front edge will be only twenty-three feet (23’) wide. The front porch, which will wrap around the front gabled section, will be six feet (6’) deep on the left side and fourteen feet (14’) deep on the right.

These proportions are compatible with those of surrounding historic houses, comprising mainly one and one-half story houses between twenty-four feet (24’) and twenty-eight feet tall (28’) and one two-story house across the street which is thirty-three feet (33’) tall. Staff finds the project to meet section II.B.1 and 2.

Setback & Rhythm of Spacing:

The house will be located on the lot so that the front setback is in keeping with the rhythm on the street established by historic houses, and with a five foot (5’) left side setback and a fourteen foot (14’) right side setback. This location allows the structure to retain and utilize an existing driveway. Although driveways are generally not common in the overlay, they are present at several historic houses on the 1400 and 1500 blocks of Ordway Place.

Staff finds that the location of the proposed new building would be compatible with the surrounding historic context and would meet guideline II.B.3.

Materials:

The new house will primarily be clad in smooth face cement fiberboard with a reveal of five inches (5”). The trim, including porch columns, window casings, and vents, will be wood. The foundation will be split-faced concrete block, and the roof will be architectural fiberglass shingles. The windows and doors will be wood, and staff asks to approve the color of the roof and the final window and door selections prior to purchase and installation. With those material specifications approved, Staff finds that the project meets section II.B.4. of the design guidelines.

Roof form:

The primary front and side gables will have a pitch of 10:12, and the front porch will have a pitch of 4:12. These roof forms are similar to those found on historic homes in the neighborhood. The project meets section II.B.5.

Orientation:

The house will be aligned with its front elevation parallel to the street, with a six foot (6') deep front porch. Staff finds that this orientation is compatible with surrounding historic houses. With a condition that a front walkway be added to connect the front porch to the public sidewalk, staff finds that the project meets design guideline II.B.6.

Proportion and Rhythm of Openings:

The windows on the house are all generally twice as tall as they are wide, and their proportions are compatible with those of historic houses. There are no large expanses of wall space on the front or sides without a window or door opening. Staff finds the project's proportion and rhythm of openings to meet Section II.B.7.

Appurtenances & Utilities:

The location of the HVAC and other utilities was not noted. Staff asks that the HVAC be located on the rear façade, or on a side façade beyond the midpoint of the house. The project meets section II.B.9.

Outbuildings:

The applicant is also proposing to construct a two-story outbuilding with a footprint of five hundred, forty-five square feet (545 sq. ft.). The garage will have a cross-gabled roof with a ridge height of twenty-five feet (25') and an eave height of fourteen feet (14'). These heights are subordinate to the primary building and compatible with those of comparable outbuildings. The materials of the new garage will match those of the house. The garage will be located behind the house, ten feet (10') from the rear property line and three feet (3') from the side, which is appropriate and meets the standard bulk zoning requirements. The project meets section II.B.8 of the design guidelines.

Recommendation:

Staff recommends approval of the application with the conditions that:

- Staff approve the color of the roof and the materials of the windows and doors;
- A walkway be added from the front porch to the street, and that the location of HVAC units and utilities be approved by Staff,

Meeting those conditions, staff finds that the proposal meets the design guidelines for the Lockeland Springs-East End Neighborhood Conservation Zoning Overlay.



Context across the street.




Two story house at 1420 Ordway Place.

INDEX OF DRAWINGS

SHEET	DRAWING TITLE
A1.0	TITLE AND SITE/ROOF PLAN
A1.1	FOUNDATION PLAN
A1.2	MAIN LEVEL PLAN
A1.3	UPPER LEVEL PLAN
A2.1	FRONT AND SIDE ELEVATIONS
A2.2	REAR AND SIDE ELEVATIONS

VICINITY MAP



BUILDING DATA


ADDRESS: 1411 ORDWAY PLACE
 NASHVILLE, TENNESSEE 37206
 PARCEL ID: 08309028900
 DESCRIPTION: LOT 6 HOLLINS HOME PLACE
 LOT AREA: .2 ACRES
 DIMENSIONS: 55' x 157'-6"
 ZONING: Residential (R6)
 PROPOSED BUILDING AREAS:

MAIN HOUSE BUILDING FOOTPRINT:	2,836 SF
MAIN HOUSE LOWER LEVEL CONDITIONED SQUARE FOOTAGE:	2,000 SF
MAIN HOUSE UPPER LEVEL CONDITIONED SQUARE FOOTAGE:	1,583 SF
MAIN HOUSE TOTAL CONDITIONED SQUARE FOOTAGE:	3,583 SF

PROJECT TEAM

ARCHITECT
 PFEFFER TORODE ARCHITECTURE
 521 8th AVENUE SOUTH, SUITE 103
 NASHVILLE, TN 37203
 615-618-3565
 jamie@pfefferarchitecture.com

1 SITE / ROOF PLAN
 SCALE 1/16" = 1'-0"



ARCHITECT:




Pfeffer Torode Architecture
 521 8th Avenue South, Nashville, Tennessee 37203
 www.pfeffertorode.com
 615-667-0808

PROJECT:
 1411 ORDWAY PLACE

1 NOVEMBER 2013

A1.0




1 MAIN LEVEL PLAN
 SCALE 1/8" = 1'-0"

ARCHITECT:
pta
 Pfeiffer Torode Architecture
 521 8th Avenue South, Nashville, Tennessee 37203
 www.pfeffertorode.com
 615-667-0808

PROJECT:
 1411 ORDWAY PLACE

1 NOVEMBER 2013

A1.2



1 SECOND LEVEL PLAN
SCALE 1/8" = 1'-0"


PROJECT:
1411 ORDWAY PLACE


ARCHITECT:




Pfeffer Torode Architecture
521 8th Avenue South, Nashville, Tennessee 37203
www.pfeffertorode.com
615-667-0808

1 NOVEMBER 2013





1 GARAGE - FIRST LEVEL FLOOR PLAN
SCALE 1/18" = 1'-0"



2 GARAGE - SECOND LEVEL FLOOR PLAN
SCALE 1/8" = 1'-0"

PROJECT:
1411 ORDWAY PLACE

ARCHITECT:




Pfeiffer Torode Architecture
521 8th Avenue South, Nashville, Tennessee 37203
www.pfeffertorode.com 615-667-0808

1 NOVEMBER 2013

A1.4



1 FRONT ELEVATION
SCALE 1/8" = 1'-0"



3 COLUMN DETAIL
SCALE 1/2" = 1'-0"



2 SIDE ELEVATION
SCALE 1/8" = 1'-0"

ARCHITECT:



Pfeiffer Torode Architecture
521 8th Avenue South, Nashville, Tennessee 37203
www.pfeffertorode.com
615-667-0808

PROJECT:
1411 ORDWAY PLACE

1 NOVEMBER 2013

A2.1



1 REAR ELEVATION
SCALE 1/8" = 1'-0"



2 SIDE ELEVATION
SCALE 1/8" = 1'-0"

ARCHITECT:
pta
 Pfeiffer Torode Architecture
 521 8th Avenue South, Nashville, Tennessee 37203
 www.pfeffertorode.com
 615-667-0808


PROJECT:
 1411 ORDWAY PLACE

1 NOVEMBER 2013

A2.2



1 GARAGE - FRONT ELEVATION
SCALE 1/8" = 1'-0"



2 GARAGE - SIDE ELEVATION
SCALE 1/8" = 1'-0"



3 GARAGE - REAR ELEVATION
SCALE 1/8" = 1'-0"



4 GARAGE - SIDE ELEVATION
SCALE 1/8" = 1'-0"

ARCHITECT:

pta

Pfeffer Torode Architecture
521 8th Avenue South, Nashville, Tennessee 37203
www.pfeffertorode.com
615-667-0808

PROJECT:

1411 ORDWAY PLACE

1 NOVEMBER 2013

A2.3