

- Exit velocities from the forebay must be non-erosive. Velocities over the weir shall be provided. If high runoff velocity is a potential problem, some type of energy dissipation device must be incorporated.
- Sediment removal in the forebay shall occur in accordance with the long-term maintenance plan.
- A fixed vertical sediment depth marker shall be installed in the forebay to measure sediment deposition over time. The marker shall be made of durable, non-corroding material (not steel). The elevation at which sediment removal is required shall be marked with a line in contrasting color or shade.
- All disturbed areas must be immediately stabilized after construction to minimize erosion.