



NOTE: MAINTAIN A MINIMUM OF 24" CLEARANCE AROUND ASSEMBLY

66" MAX. ON ASSEMBLIES 2-1/2" TO 8" CHECK WITH METRO WATER SERVICES FOR 10" ASSEMBLIES

MIN. CLEARANCE 12" PLUS PIPE DIAMETER

NOTES

- * BACKFLOW DEVICE TO REMAIN ACCESSABLE AT ALL TIMES.
- * TEST COCKS ARE TO BE PROVIDED WITH NIPPLES & CAPS.
- * STRAINER REQUIRED ON ALL DOMESTIC BACKFLOW DEVICES. (CHECK WITH FIRE MARSHALL FOR COMBINATION LINES).
- * THIS DRAWING INDICATES MINIMUM CLEARANCE AND ACCESS ONLY.
- * SECURITY PROCEDURES MAY BE DESIRABLE.
- * RISING STEM VALVES (OS&Y) ARE TO BE INSTALLED ON ANY FIRE LINES.

INSTALL ALL ITEMS ACCORDING TO MANUFACTURERS SPECIFICATIONS

METRO WATER SERVICES
BACKFLOW PREVENTER INSIDE BUILDING FOR 2-1/2" THROUGH 8" HORIZONTAL DOUBLE CHECK VALVE ASSEMBLY
 NOT TO SCALE | DATE: 7/7/04
 DWG. NO. CDETF07



Fal Baltrop
 LICENSED DISTRIBUTION OPERATOR

S. Little
 DIRECTOR OF WATER AND SEWERAGE SERVICES