

DAVID BRILEY
MAYOR



METROPOLITAN GOVERNMENT OF NASHVILLE AND DAVIDSON COUNTY

Metropolitan Historic Zoning Commission
Sunnyside in Sevier Park
3000 Granny White Pike
Nashville, Tennessee 37204
Telephone: (615) 862-7970
Fax: (615) 862-7974

STAFF RECOMMENDATION
4411 Park Avenue
August 15, 2018

Application: New Construction—Addition
District: Park and Elkins Neighborhood Conservation Zoning Overlay
Council District: 24
Map and Parcel Number: 09116004100
Applicant: Eric and Carina Jolly
Project Lead: Sean Alexander, sean.alexander@nashville.gov

Description of Project: The applicant is proposing to enlarge the house with a rear addition.

Recommendation Summary: Staff recommends approval of the proposed addition to 4411 Park Avenue with the following conditions:

1. The left side window openings shall not be not framed in; and
2. The left side dormers are revised to fit within the plane of the roof; and
3. The metal roof color and the window and door selections are approved administratively; and
4. The HVAC units and utility connections are on the rear or a non-street facing façade.

Meeting those conditions, Staff finds that the application meets the design guidelines for the Park and Elkins Neighborhood Conservation Zoning Overlay.

Attachments
A: Photographs
B: Site Plan
C: Floorplans
D: Elevations

Vicinity Map:



Aerial Map:



Applicable Design Guidelines:

II.B. NEW CONSTRUCTION AND ADDITIONS

a. Height

The height of the foundation wall, porch roof(s), and main roof(s) of a new building shall be compatible, by not contrasting greatly, with those of surrounding historic buildings.

b. Scale

The size of a new building and its mass in relation to open spaces shall be compatible, by not contrasting greatly, with surrounding historic buildings.

Most historic residential buildings have front porches. *To keep the scale appropriate for the neighborhood, porches should be a minimum of 6' deep in most cases*

Foundation lines should be visually distinct from the predominant exterior wall material. Examples are a change in material, coursing or color.

c. Setback and Rhythm of Spacing

The setback from front and side yard property lines established by adjacent historic buildings should be maintained. Generally, a dominant rhythm along a street is established by uniform lot and building width. Infill buildings should maintain that rhythm.

The Commission has the ability to determine appropriate building setbacks and extend height limitations of the required underlying base zoning for new construction, additions and accessory structures (ordinance no. 17.40.410).

Appropriate setbacks will be determined based on:

- The existing setback of the contributing primary buildings and accessory structures found in the immediate vicinity;*
- Setbacks of like structures historically found on the site as determined by historic maps, site plans or photographs;*
- Shape of lot;*
- Alley access or lack thereof;*
- Proximity of adjoining structures; and*
- Property lines.*

Appropriate height limitations will be based on:

- Heights of historic buildings in the immediate vicinity*
- Existing or planned slope and grade*

In most cases, an infill duplex should be one building, as seen historically in order to maintain the rhythm of the street. Detached infill duplexes may be appropriate in the following instances:

- There is not enough square footage to legally subdivide the lot but there is enough frontage and width to the lot to accommodate two single-family dwellings in a manner that meets the design guidelines;*
- The second unit follows the requirements of a Detached Accessory Dwelling Unit; or*
- An existing non-historic building sits so far back on the lot that a building may be constructed in front of it in a manner that meets the rhythm of the street and the established setbacks.*

d. Materials, Texture, Details, and Material Color

The materials, texture, details, and material color of a new building's public facades shall be visually compatible, by not contrasting greatly, with surrounding historic buildings. Vinyl and aluminum siding are not appropriate. MHZC does not review the painting of structures.

T-1-11- type building panels, "permastone", E.F.I.S. and other artificial siding materials are generally not appropriate. However, pre-cast stone and cement fiberboard siding are approvable cladding materials for new construction; but pre-cast stone should be of a compatible color and texture to existing historic stone clad structures in the district; and cement fiberboard siding, when used for lapped siding, should be smooth and not stamped or embossed and have a maximum of a 5" reveal. The reveal for lap siding should not exceed 5". Larger reveals may be possible but should not exceed 8" and shall have mitered corners.

Shingle siding should exhibit a straight-line course pattern and exhibit a maximum exposure of seven inches (7").

Four inch (4") nominal corner boards are required at the face of each exposed corner.

Stud wall lumber and embossed wood grain are prohibited.

Belt courses or a change in materials from one story to another are often encouraged for large two-story buildings to break up the massing.

When different materials are used, it is most appropriate to have the change happen at floor lines.

Clapboard sided chimneys are generally not appropriate. Masonry or stucco is appropriate.

Texture and tooling of mortar on new construction should be similar to historic examples.

Asphalt shingle is an appropriate roof material for most buildings. Generally, roofing should not have strong simulated shadows in the granule colors which results in a rough, pitted appearance; faux shadow lines; strongly variegated colors; colors that are too light (e.g.: tan, white, light green); wavy or deep color/texture used to simulate split shake shingles or slate; excessive flared form in the shingle tabs; uneven or sculpted bottom edges that emphasize tab width or edges, unless matching the original roof.

Generally front doors should be 1/2 to full-light. Faux leaded glass is inappropriate.

e. Roofs

The roof(s) of a new building shall be visually compatible, by not contrasting greatly, with the roof shape, orientation, and pitch of surrounding historic buildings. With the exception of chimneys, roof-top equipment and roof penetrations shall be located so as to minimize their visibility from the street.

Roof pitches should be similar to the pitches found in the district. Historic roofs are generally between 6/12 and 12/12.

Roof pitches for porch roofs are typically less steep, approximately in the 3-4/12 range.

Generally, two-story residential buildings have hipped roofs.

Generally, dormers should be located on the roof. Wall dormers are not typical in the historic context and accentuate height so they should be used minimally and generally only on secondary facades. When they are appropriate they should be no wider than the typical window openings and should not project beyond the main wall.

f. Orientation

The orientation of a new building's front facade shall be visually consistent with surrounding historic buildings.

New buildings should incorporate at least one front street-related porch that is accessible from the front street.

Side porches or porte cocheres may also be appropriate as a secondary entrance, but the primary entrance should address the front.

Front porches generally should be a minimum of 6' deep, have porch racks that are 1'-3' tall and have posts that include bases and capitals.

Parking areas and Driveways

Generally, curb cuts should not be added.

Where a new driveway is appropriate it should be two concrete strips with a central grassy median. Shared driveways should be a single lane, not just two driveways next to each other. Sometimes this may be accomplished with a single lane curb cut that widens to a double lane deeper into the lot.

g. Proportion and Rhythm of Openings

The relationship of width to height of windows and doors, and the rhythm of solids (walls) to voids (door and window openings) in a new building shall be compatible, by not contrasting greatly, with surrounding historic buildings.

Window openings on the primary street-related or front façade of new construction should be representative of the window patterns of similarly massed historic structures within the district.

In most cases, every 8-13 horizontal feet of flat wall surface should have an opening (window or door) of at least 4 square feet. More leniencies can be given to minimally visible side or rear walls.

Double-hung windows should exhibit a height to width ratio of at least 2:1.

Windows on upper floors should not be taller than windows on the main floor since historically first floors have higher ceilings than upper floors and so windows were typically taller on the first floor.

Single-light sashes are appropriate for new construction. If using multi-light sashes, muntins should be fully simulated and bonded to the glass, and exhibit an interior bar, exterior bar, as well as a spacer between glass panes.

Four inch (nominal) casings are required around doors, windows and vents on non-masonry buildings.

Trim should be thick enough to extend beyond the clapboard. Double or triple windows should have a 4" to 6" mullion in between.

Brick molding is required around doors, windows and vents within masonry walls but is not appropriate on non-masonry buildings.

h. Utilities

Utility connections such as gas meters, electric meters, phone, cable, and HVAC condenser units should be located so as to minimize their visibility from the street.

Generally, utility connections should be placed no closer to the street than the mid point of the structure.

Power lines should be placed underground if they are carried from the street and not from the rear or an alley.

2. ADDITIONS

- a. Generally, an addition should be situated at the rear of a building in such a way that it will not disturb either front or side facades. To distinguish between the historic structure and an addition, it is desirable to set the addition in from the building side wall or for the addition to have a different exterior cladding. Additions not normally recommended on historic structures may be appropriate for non-historic structures. Front or side alterations to non-historic structures that increase space or change exterior height should be compatible by not contrasting greatly with adjacent historic buildings.

Placement

- Additions should be located at the rear of an existing structure.

Placement

Additions should be located at the rear of an existing structure.

Connections to additions should, as much as possible, use existing window and door openings rather than remove significant amounts of rear wall material. Generally, one-story rear additions should inset one foot, for each story, from the side wall. Additions should be physically distinguished from the historic building and generally fit within the shadow line of the existing building.

In order to assure that an addition has achieved proper scale, the addition should:

- No matter their use, not be larger than the existing house, not including non-historic additions, in order to achieve compatibility in scale. This will allow for the retention of small and medium size homes in the neighborhood. The diversity of housing type and size is a character defining feature of the historic districts.*
- Additions which are essentially a house-behind-a-house with a long narrow connector are not appropriate, as the form does not exist historically. Short or minimal connections that do not require the removal of the entire back wall of a historic building are preferred.*
- When an addition ties into an existing roof it should be a minimum of 6" off the existing ridge.*
- Generally be shorter and thinner than the existing building. Exceptions may be made when unusual constraints make these parameters unreasonable, such as:*
 - An extreme grade change*
 - Atypical lot parcel shape or size**In these cases, an addition may rise above or extend wider than the existing building; however, generally the addition should not higher and extend wider.*

When an addition needs to be taller:

Whenever possible, additions should not be taller than the historic building; however, when a taller addition is the only option, additions to single story structures may rise as high as 4' above the shadow line of the existing building at a distance of 40' from the front edge of the existing building. In this instance, the side walls and roof of the addition must set in as is typical for all additions. The portion of the roof that can be seen should have a hipped, side gable or clipped gable roof to help decrease the visual mass of the addition.

When an addition needs to be wider:

Rear additions that are wider than an existing historic building may be appropriate when the building is narrower than 30' or shifted to one side of the lot. In these instances, a structural alcove or channel must separate the existing building from the new addition. The structural alcove should sit in a minimum of 1' and be at least twice as long as it is deep.

In addition, a rear addition that is wider should not wrap the rear corner.

Ridge raises

Ridge raises are most appropriate for one-story, side-gable buildings, (without clipped gables) and that require more finished height in the attic. The purpose of a ridge raise is to allow for conditioned space in the attic and to discourage large rear or side additions. The raised portion must sit in a minimum of 2' from each side wall and can be raised no more than 2' of total vertical height within the same plane as the front roof slope.

Sunrooms

Metal framed sunrooms, as a modern interpretation of early green houses, are appropriate if they are mostly glass or use appropriate cladding material for the district, are located at the rear in a minimally visible location, are minimally attached to the existing structure, and follow all other design guidelines for additions.

Foundation

Foundation walls should set in from the existing foundation at the back edge of the existing structure

by one foot for each story or half story. Exception: When an addition is a small one-room deep (12' deep or less) addition that spans the width of the structure, and the existing structure is masonry with the addition to be wood (or appropriate substitute siding). The change in material from masonry to wood allows for a minimum of a four inch (4") inset.

Foundation height should match or be lower than the existing structure.

Foundation lines should be visually distinct from the predominant exterior wall material. This is generally accomplished with a change in materials.

Roof

The height of the addition's roof and eaves must be less than or equal to the existing structure.

Visually evident roof slopes should match the roof slopes of the existing structure, and roof planes should set in accordingly for rear additions.

Skylights should not be located on the front-facing slope of the roof. Skylights should be flat (no bubble lenses) with a low profile (no more than six inches tall) and only be installed behind the midpoint of the building).

Dormers

Dormer additions are appropriate for some historic buildings as they are a traditional way of adding ventilation and light to upper stories.

The addition of a dormer that would require the removal of historic features such as an existing dormer, chimneys, cupolas or decorative feature is not appropriate.

Rear dormers should be inset from the side walls of the building by a minimum of two feet. The top of a rear dormer may attach just below the ridge of the main roof or lower.

Front & Side dormers should be compatible with the scale and design of the building. Generally, this can be accomplished with the following:

- *New dormers should be similar in design and scale to an existing dormer on the building.*
- *New dormers should be similar in design and scale to an existing dormer on another historic building that is similar in style and massing.*
- *The number of dormers and their location and size should be appropriate to the style and design of the building. Sometimes dormer locations relate to the openings below. The symmetry or lack of symmetry within a building design should be used as a guide when placing dormers.*
- *Dormers should not be added to secondary roof planes.*
- *Eave depth on a dormer should not exceed the eave depth on the main roof.*
- *The roof form of the dormer should match the roof form of the building or be appropriate for the style.*
- *The roof pitch of the dormer should generally match the roof pitch of the building.*
- *The ridge of a side dormer should be at least 2' below the ridge of the existing building; the cheeks should be inset at least 2' from the wall below or adjacent valley; and the front wall of the gable should setback a minimum of 2' from the wall below. (These minimum insets will likely be greater than 2' when following the guidelines for appropriate scale.)*
- *Dormers should generally be fully glazed and aprons below the window should be minimal.*
- *The exterior material cladding of side dormers should match the primary or secondary material of the main building.*

Side Additions

- b. When a lot width exceeds 60 feet or the standard lot width on the block, it may be appropriate to add a side addition to a historic structure. The addition should set back from the face of the historic structure and should be subservient in height, width and massing to the historic structure.

Side additions should be narrower than half of the historic building width and exhibit a height of at least 2' shorter than the historic building.

To deemphasize a side addition, the roofing form should generally be a hip or side-gable roof form.

c. The creation of an addition through enclosure of a front porch is not appropriate. The creation of an addition through the enclosure of a side porch may be appropriate if the addition is constructed in such a way that original form and openings on the porch remain visible and undisturbed.

Side porch additions may be appropriate for corner building lots or lots more than 60' wide.

d. Contemporary designs for additions to existing properties are not discouraged when such additions do not destroy significant historical, architectural, or cultural material; and when such design is compatible, by not contrasting greatly, with the size, scale, color, material, and character of the property, neighborhood, or environment.

e. A new addition should be constructed in such a manner that if the addition were to be removed in the future, the essential form and integrity of the original structure would be unimpaired.

Connections should, as much as possible, use existing window and door openings rather than remove significant amounts of rear wall material.

f. Additions should follow the guidelines for new construction.

III.B. DEMOLITION

1. Demolition is not appropriate
 - a. if a building, or major portion of a building, is of such architectural or historical interest and value that its removal would be detrimental to the public interest; or
 - b. if a building, or major portion of a building, is of such old or unusual or uncommon design and materials that it could not be reproduced or be reproduced without great difficulty and expense.

2. Demolition is appropriate
 - a. if a building, or major portion of a building, has irretrievably lost its architectural and historical integrity and significance and its removal will result in a more historically appropriate visual effect on the district;
 - b. if a building, or major portion of a building, does not contribute to the historical and architectural character and significance of the district and its removal will result in a more historically appropriate visual effect on the district; or

Generally, non-historic (non-contributing) structures may be demolished for new construction that will have a more historically appropriate effect on the district.

- c. if the denial of the demolition will result in an economic hardship on the applicant as determined by the MHZC in accordance with section 17.40.420 (Historic Zoning Regulations), Metropolitan Comprehensive Zoning Ordinance.

Background: The building at 4411 Park Avenue is a one and one-half story Transitional Victorian house with a pyramidal roof and a wrap-around corner porch. The house was constructed circa 1910, and is a contributing building because of its age and architectural character.



4411 Park Avenue

The house was enlarged with a rear addition prior to the creation of the overlay and all of the house's windows have been replaced with vinyl windows.

Analysis and Findings: The applicant is proposing to enlarge the house with a new rear addition.

Demolition: Portions of the rear wall and right side wall of the earlier addition will be demolished to accommodate the new addition, along with portions of the rear slope of the main roof. Because they are at the rear or are not original, these sections of the building do not contribute to its historic character. Staff finds that the partial demolition meets section III.B.2 for appropriate demolition and does not meet section III.B.1 for inappropriate demolition.

The plans show two existing window openings on the left side depicted with closed shutters. Installing operable shutters may be appropriate, but framing in the windows and installing false shutters would be considered inappropriate partial demolition. With the condition that the side window openings are not framed in, Staff finds that the partial demolition meets section III.B.2 for appropriate demolition and does not meet section III.B.1 for inappropriate demolition.

Location & Removability: The new addition will be located behind the rear of the historic house, tying in to the side of the existing addition and in to the rear slope of the original roof. The addition will be stepped in from the right side of the house by one foot (1') and go back with a two foot (2') deep alcove before stepping back out to the right. The existing rear addition is flush with the left side of the house, and no change to its footprint on that side is proposed.

The addition will also include two dormers on the left side of the house, one on the original roof and one on the roof of the earlier addition. Both of these locations would be appropriate for dormer additions, however Staff recommends that they are set two feet (2') in from the first story wall below and down off of the original roof ridges so as to not impact the original roof lines.

With a condition that the dormers are revised to fit within the plane of the roof, Staff finds that the location of the addition is appropriate and that the project meets sections II.B.2.a and II.B.2.e of the design guidelines.

Design: The character of the addition will be similar to that of the existing house, with a similar roof form, window pattern, and matching exterior materials. The addition will be sufficiently differentiated from the original building by the right side wall stepping in with an alcove so as to be physically distinguishable from the historic house. Staff finds that the project meets section II.B.2.a and II.B.2.f of the design guidelines.

Height & Scale: The addition will include a gabled roof matching the height of the existing primary roof, with a twenty-two foot (22') span between them connected by a ridge sitting sixteen inches (16") lower. The new gable will sit outside the silhouette of the house to the right as depicted on the front elevation, however, because it is so far back and does not directly impact the building's original form, Staff finds it to be appropriate.

At the first story level behind the existing building, the new addition will step out to the right side of the existing side wall five feet (5') wider than the historic house. Staff finds the additional width to be appropriate because it originates behind the rear of the original structure and because the lot is wider than the standard lot size for the area. The lot is sixty-one feet (61') wide.



View of 4411 Park Avenue from right-rear.

A covered porch will also tie in to the new and existing additions, extending two feet (2') beyond the existing rear wall of the house. Staff finds the increased depth will not impact the historic character of the house as the porch is minimal and primarily open in nature.

Staff finds that the height and scale of the proposed addition is appropriate and that the project meets sections II.B.1.a and II.B.1.b of the design guidelines.

Setback & Rhythm of Spacing: Where it is wider than the existing house on the right side, the addition will have an actual side setback of seven feet (7') but it will appear to have a forty foot (40') setback because of the unimproved right-of-way adjacent to the lot. The new rear porch will increase the depth of the house by two feet (2') giving it a setback of forty feet (40') and leaving twenty feet (20') between the house and the existing garage. Staff finds that the addition will not disrupt the established pattern of spacing between buildings on the street. Staff finds that the project meets section II.B.1.c of the design guidelines.

Materials:

	Proposed	Color/Texture/ Make/ Manufacturer	Approved Previously or Typical	Requires Additional Review
Foundation	Concrete Block	Parged to Match Existing	Yes	
Cladding	Cement-fiber Clapboard	Smooth, Match Existing Reveal	Yes	
Trim	Cement Fiber, Wood	Smooth faced	Yes	
Primary Roofing	Asphalt Shingles	Match Existing	Yes	
Porch & Secondary Roofing	Metal, Standing Seam	Color Not Indicated	Yes	X
Porch floor/steps	Concrete	Typical	Yes	
Porch Columns	Wood	Smooth	Yes	
Windows	Wood	Approval Needed	Not Known	X
Rear Door	Not indicated	Approval Needed	Not Known	X

With the condition that the metal roof color and the window and door selections are approved administratively, Staff finds that the proposal meets section II.B.1.d of the design guidelines.

Roof form: The addition’s roof will have two gables facing to the right, matching the 12:12 pitch of the original roof and the existing addition. As described above, two dormers are to be added on the left side of the house, which would also be gabled with a 12:12 pitch. The porch roof will have a 6:12 pitch, which is typical of the roofs on similar porch forms.

With a condition that the new left side dormers are revised to fit within the plane of the roof, Staff finds that that the roofs of the proposed addition are appropriate and that the project meets section II.B.1.e of the design guidelines.

Proportion and Rhythm of Openings: No changes to windows and doors, other than the proposal to enclose windows discussed under “demolition” are indicated on the plans.

The windows on the proposed addition are all generally twice as tall as they are wide, thereby meeting the historic proportions of openings. There are no large expanses of wall space without a window or door opening.

Staff finds that the proportion and rhythm of openings meet section II.B.1.g of the design guidelines.

Appurtenances & Utilities: No changes to the site's appurtenances were indicated on the drawings. The location of the HVAC and other utilities was not noted. If they are relocated, Staff asks that the HVAC be located on the rear façade, or on a side façade beyond the midpoint of the house. With that condition, Staff finds that the project meets section II.B.1.h of the design guidelines.

Recommendation: Staff recommends approval of the proposed addition to 4411 Park Avenue with the following conditions:

1. The left side window openings shall not be not framed in; and
2. The left side dormers are revised to fit within the plane of the roof; and
3. The metal roof color and the window and door selections are approved administratively; and
4. The HVAC units and utility connections shall be on the rear or a non-street facing façade.

Meeting those conditions, Staff finds that the application meets the design guidelines for the Park and Elkins Neighborhood Conservation Zoning Overlay.

PHOTOGRAPHS



4411 Park Avenue, front.



4411 Park Avenue, from corner showing unimproved right-of-way to the right.



4411 Park Avenue, right façade showing existing rear addition.



4411 Park Avenue, left side.

SURVEYOR'S CERTIFICATE:

I HEREBY CERTIFY THAT THIS LOT SURVEY IS A CATEGORY I SURVEY; THAT THE SURVEY WAS PERFORMED IN ACCORDANCE WITH THE CURRENT STANDARDS OF PRACTICE FOR LAND SURVEYORS IN THE STATE OF TENNESSEE (UNDER THE AUTHORITY OF TCA 62-18-126), AND THE UNADJUSTED ERROR OF CLOSURE EXCEEDS 1:10,000 AS SHOWN HEREON.

BY: ADVANTAGE LAND SURVEYING DATE: JUNE 22, 2018

PROPERTY TITLE REFERENCE:

THE SURVEYED PREMISES IS ALL OF THE SAME PROPERTY AS CONVEYED TO: CARINA JOLLY AND ERIC JOLLY, HUSBAND AND WIFE, FROM EVAN BEZIAT AND ASHLEY BEZIAT, HUSBAND AND WIFE, AS OF RECORD IN WARRANTY DEED # 20180529-0050729, REGISTER'S OFFICE, DAVIDSON COUNTY, TENNESSEE.

9150 Sq. Feet
0.21 Acres


EXISTING IMPERVIOUS AREAS:

CONCRETE SIDEWALK: 196 SQ. FT.
EXISTING RESIDENCE: 2495 SQ. FT.
CONCRETE PADS: 28 SQ. FT.
CONCRETE DRIVE: 669 SQ. FT.
GARAGE: 442 SQ. FT.
WOOD DECK: 220 SQ. FT.
ENCLOSED CRAWLSPACE ENTRANCE: 17 SQ. FT.
PORCH: 278 SQ. FT.

TOTAL AREA: 4346 SQ. FT.

GENERAL NOTES:

1. BEARINGS SHOWN ARE BASED ON MAGNETIC NORTH.
2. THE TOTAL AREA WITHIN THE SURVEYED PREMISES IS 9,150 S.F.± OR 0.21 OF AN ACRE, MORE OR LESS.
3. ALL LOT / PROPERTY CORNERS ARE MARKED AS SHOWN ON THIS SURVEY.
4. ALL BUILDING & ENCROACHMENT TIE DIMENSIONS ARE PERPENDICULAR TO THE PROPERTY LINES. ALL MBSL'S AS SHOWN HEREON ARE BASED ON THE CURRENT ZONING CODE. SEE BUILDING SETBACK NOTE, THIS SHEET.
5. PARCEL NUMBERS SHOWN THUS (41.00) PERTAIN TO DAVIDSON COUNTY PROPERTY MAP # 91-16. ACCORDING TO METRO GIS WEB SITE THE SURVEYED PREMISES IS PRESENTLY ZONED; R8.
6. BY GRAPHIC PLOTTING AND MAP SCALING LOCATION ONLY, THIS PROPERTY IS NOT WITHIN AN AREA OF FLOOD INUNDATION AS DESIGNATED BY CURRENT FEDERAL EMERGENCY MANAGEMENT AGENCY MAPS (FEMA) WHICH MAKE UP A PART OF THE NATIONAL FLOOD INSURANCE ADMINISTRATION REPORT AS SHOWN ON FEMA MAP ORDER NUMBER 47037C0239H WHICH IS THE MOST CURRENT (VIA THE FEMA WEB-SITE) FOR WHICH THE SURVEYED PREMISES IS SITUATED IN. THE SURVEYED PREMISES LIES ENTIRELY WITHIN ZONE "X". REVISED DATE: 4-05-2017.
7. THIS SURVEYOR HAS NOT PHYSICALLY LOCATED ANY UNDERGROUND UTILITIES. ABOVE GRADE AND UNDERGROUND UTILITIES SHOWN HEREON WERE TAKEN FROM VISIBLE APPURTENANCES AT THE SITE, PUBLIC RECORDS, AND/OR MAPS PREPARED BY OTHERS. THIS SURVEYOR MAKES NO GUARANTEE THAT THE UNDERGROUND UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. THIS SURVEYOR FURTHER DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION AS INDICATED. THEREFORE, RELIANCE UPON THE TYPE, SIZE AND LOCATION OF ALL UNDERGROUND UTILITIES SHOULD BE DONE SO WITH THIS CIRCUMSTANCE CONSIDERED. DETAILED VERIFICATION OF EXISTENCE, LOCATION AND DEPTH SHOULD ALSO BE MADE PRIOR TO ANY DECISION RELATIVE THERETO IS MADE. AVAILABILITY AND COST OF SERVICE SHOULD BE CONFIRMED WITH THE APPROPRIATE UTILITY COMPANY. COORDINATE WITH TENNESSEE ONE-CALL SYSTEM, INC. - PHONE: 811.
8. ANY EXCAVATION, FILL OR DISTURBANCE OF THE EXISTING GROUND ELEVATION MUST BE DONE IN ACCORDANCE WITH STORM WATER MANAGEMENT ORDINANCE NO. 78-840 AND APPROVED BY THE METROPOLITAN DEPARTMENT OF WATER SERVICES.
9. SIZE DRIVEWAY CULVERTS PER THE DESIGN CRITERIA SET FORTH BY THE METRO STORM WATER MANAGEMENT MANUAL. (MINIMUM DRIVEWAY CULVERT SIZE IN METRO R.O.W. IS 15" CMP).
10. ANY DEVELOPMENT OF THIS PROJECT SHALL COMPLY WITH REQUIREMENTS OF THE ADOPTED TREE ORDINANCE 094-1104 (METRO CODE CHAPTER 17.24. ARTICLE II, TREE PROTECTION AND REPLACEMENT; CHAPTER 17.40, ARTICLE X, TREE PROTECTION AND REPLACEMENT PROCEDURES).
11. THIS SURVEYOR HAS MADE NO INVESTIGATION OR INDEPENDENT SEARCH FOR EASEMENTS OF RECORD, ENCUMBRANCES, RESTRICTIVE COVENANTS, OWNERSHIP TITLE EVIDENCE OR ANY OTHER FACTS THAT AN ACCURATE AND CURRENT TITLE SEARCH / REPORT MAY DISCLOSE.; THEREFORE, THIS SURVEY IS SUBJECT TO ALL MATTERS THAT AN ACCURATE AND CURRENT TITLE SEARCH MAY REVEAL.
12. THE SURVEYED PREMISES IS SUBJECT TO ALL GOVERNMENTAL AGENCIES REQUIREMENTS FOR ANY TYPE OF EXCAVATION, IMPROVEMENTS, DEMOLITION OR NEW CONSTRUCTION.



ALLEY # 1198
(20' PUBLIC R/W)



(SEE NOTE 1)

45TH AVENUE NORTH
(100' PUBLIC R/W)

N.E.S. NOTE:

N.E.S HAS AUTHORITY TO CLEAR OR TRIM ANYTHING WITHIN 5' TO 10' OF A POWER LINE, WHETHER OF RECORD EASEMENT OR NOT, EVEN IF THE POWER LINE IS NOT CENTERED DIRECTLY WITHIN THE EASEMENT.

BUILDING SETBACK NOTE:

ALL MBSL DISTANCES AS SHOWN HEREON ARE SUBJECT TO THE ZONING CODE AND WILL HAVE TO BE APPROVED BY THE CODES DEPARTMENT PRIOR TO CONSTRUCTION.


SPECIAL NOTE:

ANY ENCROACHMENTS ON TO THIS PROPERTY ARE SUBJECT TO A CLAIM OF ADVERSE POSSESSION BY ADJOINING PROPERTY OWNERS, AND VICE VERSA. POSSESSION CAN BE ADVERSE EVEN IF DUE TO A MISTAKE.

PROPERTY ADDRESS:

4411 PARK AVENUE
NASHVILLE, TN. 37209


PREPARED BY:
ADVANTAGE LAND SURVEYING
4636 LEBANON PIKE # 327
HERMITAGE, TENNESSEE 37076
PHONE # 615-319-4701




SIGNED: _____
NAME: WILLIAM B. PERKINS
TENNESSEE R.L.S. # 2163

LOT SURVEY
LOT 312 OF BLOCK 13 ON THE PLAN OF
CHARLOTTE PARK ADDITION
TO WEST NASHVILLE

RECORDED IN PLAT BOOK 57, PAGE 103 R.O.D.C., TN.
24th COUNCIL DISTRICT - METROPOLITAN NASHVILLE,
DAVIDSON COUNTY, TENNESSEE




DRAWN BY: BILLY PERKINS
CHECKED BY: ROSA PEREZ




4411 PARK AVE.

SHEET NUMBER
A-1




2ND FLOOR



4411 PARK AVE.

SHEET NUMBER
A-1



NOT FOR CONSTRUCTION
 CONCEPT and GOVERNING
 APPROVAL ONLY

SCALE : 1/4" = 1'-0"


4411 PARK AVE.

SHEET NUMBER
 A-3



NOT FOR CONSTRUCTION
 CONCEPT and GOVERNING
 APPROVAL ONLY

RIGHT SIDE



4411 PARK AVE.

SHEET NUMBER
 A-4

