

JOHN COOPER
MAYOR



METROPOLITAN GOVERNMENT OF NASHVILLE AND DAVIDSON COUNTY

Metropolitan Historic Zoning Commission
Sunnyside in Sevier Park
3000 Granny White Pike
Nashville, Tennessee 37204
Telephone: (615) 862-7970

STAFF RECOMMENDATION

1510 Holly Street

August 19, 2020

Application: New Construction—Infill and Outbuilding/Detached Accessory Dwelling Unit

District: Lockeland Springs-East End Neighborhood Conservation Zoning Overlay

Council District: 06

Base Zoning: R6

Map and Parcel Number: 08313037200

Applicant: Legacy South Builders

Project Lead: Melissa Baldock, melissa.baldock@nashville.gov

Description of Project: The applicant proposes a rear addition and a new outbuilding (Detached Accessory Dwelling Unit). 1510 Holly sustained damage in the March 3, 2020 tornado, and its existing garage was demolished during the storm.

Recommendation Summary: Staff recommends approval of the project with the condition that staff approve a brick sample, the garage door, and the HVAC location prior to purchase and installation. With these conditions, staff finds that the proposed addition and DADU meet Sections II.B. and III.B. of the design guidelines and 17.16.030.G, the DADU ordinance.

Attachments

A: Photographs

B: Site Plan

C: Elevations

Vicinity Map:



Aerial Map:



Applicable Design Guidelines:

II.B. New Construction

1. Height

New buildings must be constructed to the same number of stories and to a height which is compatible with the height of adjacent buildings.

The height of the foundation wall, porch roof, and main roofs should all be compatible with those of surrounding historic buildings.

Infill construction on the 1400 -1600 blocks of Boscobel Street may be up to two-stories.

For those lots located within the Five Points Subdistrict of the Five Points Redevelopment District new buildings shall not exceed 2 stories and 30' in height. A third story and 15' may be added provided that is for residential use only and is compatible with existing adjacent historic structures. The third story must be stepped back at least 10' from façade planes facing a residential subdistrict, an existing house (regardless of use), and public streets. All front and side building walls shall be a minimum of 20' in height. For multi-story buildings, the minimum first floor height shall be 14' from finished floor to finished floor. Exception: buildings with first floor residential use, minimum first floor height shall be 12'.

For those lots located within the Corner Commercial Subdistrict of the Five Points Redevelopment District new buildings shall not exceed 2 stories and 30' in height. An additional story may be added to a building provided that, where it is adjacent to a detached house or a residential subdistrict, it is set back a minimum of 25' from the building wall or 50' from the property line. Three story building height shall not exceed 45'. All front and side buildings walls shall be a minimum of 16' in height and at the build-to line. For multi-story buildings, the minimum first floor height shall be 14' from finished floor to finished floor.

For those lots located within the Residential Subdistrict of the Five Points Redevelopment District shall not exceed 3 stories .

2. Scale

The size of a new building and its mass in relation to open spaces; and its windows, doors, openings, and porches should be visually compatible with surrounding historic buildings.

Foundation lines should be visually distinct from the predominant exterior wall material. This is typically accomplished with a change in material.

3. Setback and Rhythm of Spacing

4. Since construction in an historic district has usually taken place continuously from the late nineteenth and early twentieth centuries, a variety of building types and styles result which demonstrate the changes in building tastes and technology over the years. New buildings should continue this tradition while complementing and being compatible with other buildings in the area.

In Lockeland Springs-East End, historic buildings were constructed between 1880 and 1950. New buildings should be compatible with surrounding houses from this period.

5. Reconstruction may be appropriate when it reproduces facades of a building which no longer exists and which was located in the historic district if: (1) the building would have contributed to the

historical and architectural character of the area; (2) if it will be compatible in terms of style, height, scale, massing, and materials with the buildings immediately surrounding the lot on which the reproduction will be built; and (3) if it is accurately based on pictorial documentation.

6. Because new buildings usually relate to an established pattern and rhythm of existing buildings, both on the same and opposite sides of a street, the dominance of that pattern and rhythm must be respected and not disrupted.
7. New construction should be consistent with existing buildings along a street in terms of height, scale, setback, and rhythm; relationship of materials, texture, details, and color; roof shape; orientation; and proportion and rhythm of openings.

The setback from front and side yard property lines established by adjacent historic buildings must be maintained. When a definite rhythm along a street is established by uniform lot and building width, infill new buildings should maintain that rhythm.

The Commission has the ability to reduce building setbacks and extend height limitations of the required underlying base zoning for new construction, additions and accessory structures (ordinance no. 17.40.410).

Appropriate setback reductions will be determined based on:

- The existing setback of the contributing primary buildings and accessory structures found in the immediate vicinity;*
- Setbacks of like structures historically found on the site as determined by historic maps, site plans or photographs;*
- Shape of lot;*
- Alley access or lack thereof;*
- Proximity of adjoining structures; and*
- Property lines.*

Appropriate height limitations will be based on:

- Heights of historic buildings in the immediate vicinity*
- Existing or planned slope and grade*

Infill construction on the 1400 - 1600 blocks of Boscobel Street may have widths up to 40'.

4. Relationship of Materials, Textures, Details, and Material Colors

The relationship and use of materials, textures, details, and material color of a new building's public facades shall be visually compatible with and similar to those of adjacent buildings, or shall not contrast conspicuously.

T-1-11- type building panels, "permastone", E.F.I.S. and other artificial siding materials are generally not appropriate. However, pre-cast stone and cement fiberboard siding are approvable cladding materials for new construction; but pre-cast stone should be of a compatible color and texture to existing historic stone clad structures in the district; and cement fiberboard siding, when used for lapped siding, should be smooth and not stamped or embossed and have a maximum of a 5" reveal. The reveal for lap siding should not exceed 5". Larger reveals may be possible but should not exceed 8" and shall have mitered corners.

Shingle siding should exhibit a straight-line course pattern and exhibit a maximum exposure of seven inches (7").

Four inch (4") nominal corner boards are required at the face of each exposed corner.

Stud wall lumber and embossed wood grain are prohibited.

Belt courses or a change in materials from one story to another are often encouraged for large two-story buildings to break up the massing.

When different materials are used, it is most appropriate to have the change happen at floor lines. Clapboard sided chimneys are generally not appropriate. Masonry or stucco is appropriate. Texture and tooling of mortar on new construction should be similar to historic examples. Asphalt shingle is an appropriate roof material for most buildings. Generally, roofing should not have strong simulated shadows in the granule colors which results in a rough, pitted appearance; faux shadow lines; strongly variegated colors; colors that are too light (e.g.: tan, white, light green); wavy or deep color/texture used to simulate split shake shingles or slate; excessive flared form in the shingle tabs; uneven or sculpted bottom edges that emphasize tab width or edges, unless matching the original roof. Primary entrances should be 1/2 to full-light doors. Faux leaded glass is inappropriate. Generally front doors should be 1/2 to full-light. Faux leaded glass is inappropriate.

5. Roof Shape

The roofs of new buildings shall be visually compatible, by not contrasting greatly, with the roof shape and orientation of surrounding buildings.

Roof pitches should be similar to the pitches found in the district. Historic roofs are generally between 6/12 and 12/12.

Roof pitches for porch roofs are typically less steep, approximately in the 3-4/12 range.

Generally, two-story residential buildings have hipped roofs.

Generally, dormers should be located on the roof. Wall dormers are not typical in the historic context and accentuate height so they should be used minimally and generally only on secondary facades. When they are appropriate they should be no wider than the typical window openings and should not project beyond the main wall.

Infill construction on the 1400 -1600 blocks of Boscobel Street may have flat roofs or roofs with a minimal slope.

6. Orientation

The site orientation of new buildings shall be consistent with that of adjacent buildings and shall be visually compatible. Directional expression shall be compatible with surrounding buildings, whether that expression is vertical, horizontal, or non-directional.

Porches

New buildings should incorporate at least one front street-related porch that is accessible from the front street.

Side porches or porte cocheres may also be appropriate as a secondary entrance, but the primary entrance should address the front.

Front porches generally should be a minimum of 6' deep, have porch racks that are 1'-3' tall and have posts that include bases and capitals.

Parking areas and Driveways

Generally, curb cuts should not be added.

Where a new driveway is appropriate it should be two concrete strips with a central grassy median.

Shared driveways should be a single lane, not just two driveways next to each other. Sometimes this may be accomplished with a single lane curb cut that widens to a double lane deeper into the lot.

Duplexes

Infill duplexes shall have one or two doors facing the street, as seen on historic duplexes. In the case of corner lots, an entrance facing the side street is possible as long as it is designed to look like a secondary entrance.

In the case of duplexes, vehicular access for both units should be from the alley, where an alley exists. A new shared curb cut may be added, if no alley and no driveway exists, but the driveway should be no more than 12' wide from the street to the rear of the home. Driveways should use concrete strips where they are typical of the historic context. Front yard parking or driveways which end at the front of the house are not consistent with the character of the historic neighborhoods.

7. Proportion and Rhythm of Openings

The relationship of width to height of windows and doors, and the rhythm of solids (walls) to voids (door and window openings) in a new building shall be compatible, by not contrasting greatly, with surrounding historic buildings.

Window openings on the primary street-related or front façade of new construction should be representative of the window patterns of similarly massed historic structures within the district. In most cases, every 8-13 horizontal feet of flat wall surface should have an opening (window or door) of at least 4 square feet. More leniencies can be given to minimally visible side or rear walls.

Double-hung windows should exhibit a height to width ratio of at least 2:1.

Windows on upper floors should not be taller than windows on the main floor since historically first floors have higher ceilings than upper floors and so windows were typically taller on the first floor.

Single-light sashes are appropriate for new construction. If using multi-light sashes, muntins should be fully simulated and bonded to the glass, and exhibit an interior bar, exterior bar, as well as a spacer between glass panes.

Four inch (nominal) casings are required around doors, windows and vents on non-masonry buildings.

Trim should be thick enough to extend beyond the clapboard. Double or triple windows should have a 4" to 6" mullion in between.

Brick molding is required around doors, windows and vents within masonry walls but is not appropriate on non-masonry buildings.

8. Outbuildings

(Although the MHZC does not review use itself there are additional ordinance requirements for buildings that are or have a Detached Accessory Dwelling Unit (DADU) required by ordinance 17.16.030 that are reviewed by the MHZC. This information is provided for informational purposes only and does not replace ordinance 17.16.030.)

- a. Garages and storage buildings should reflect the character of the existing house and surrounding buildings and should be compatible in terms of height, scale, roof shape, materials, texture, and details.

Outbuildings: Height & Scale

- *On lots less than 10,000 square feet, the footprint of a DADU or outbuilding shall not exceed seven hundred fifty square feet or fifty percent of the first floor area of the principal structure, whichever is less.*
- *On lots 10,000 square feet or greater, the footprint of a DADU or outbuilding shall not exceed one thousand square feet.*
- *The DADU or outbuilding shall maintain a proportional mass, size, and height to ensure it is not taller or wider than the principal structure on the lot. The DADU or outbuilding height shall not exceed the height of the principal structure, with a maximum eave height of 10' for one-story DADU's or outbuildings and 17' for two-story DADUs or outbuildings. The roof ridge height of the DADU or outbuilding must be less than the principal building and shall not exceed 25' feet in height.*

Outbuildings: Character, Materials and Details

- *Historically, outbuildings were either very utilitarian in character, or (particularly with more extravagant houses) they repeated the roof forms and architectural details of the houses to which they related. Generally, either approach is appropriate for new outbuildings. DADUs or out buildings located on corner lots should have similar architectural characteristics, including roof form and pitch, to the existing*

principal structure.

· DADUs or outbuildings with a second story shall enclose the stairs interior to the structure and properly fire rate them per the applicable life safety standards found in the code editions adopted by the Metropolitan Government of Nashville.

Outbuildings: Roof

· Roof slopes on simple, utilitarian buildings do not have to match the roof slopes of the main structure, but generally should maintain at least a 4/12 pitch.
· The DADU or outbuilding may have dormers that relate to the style and proportion of windows on the DADU and shall be subordinate to the roof slope by covering no more than fifty percent of the roof plane and should sit back from the exterior wall by 2'.

Outbuildings: Windows and Doors

· Publicly visible windows should be appropriate to the style of the house.
· Double-hung windows are generally twice as tall as they are wide and of the single-light sash variety.
· Publicly visible pedestrian doors must either be appropriate for the style of house to which the outbuilding relates or be flat with no panels.
· Metal overhead doors are acceptable on garages when they are simple and devoid of overly decorative elements typical on high-style wooden doors. Decorative raised panels on publicly visible garage doors are generally not appropriate.
· For street-facing facades, garages with more than one-bay should have multiple single doors rather than one large door to accommodate more than one bay.

Outbuildings: Siding and Trim

· Brick, weatherboard, and board-and-batten are typical siding materials.
· Exterior siding may match the existing contributing building's original siding; otherwise, siding should be wood or smooth cement-fiberboard lap siding with a maximum exposure of five inches (5"), wood or smooth cement-fiberboard board-and-batten or masonry.
· Four inch (4" nominal) corner-boards are required at the face of each exposed corner.
· Stud wall lumber and embossed wood grain are prohibited.
· Four inch (4" nominal) casings are required around doors, windows, and vents within clapboard walls. Trim should be thick enough to extend beyond the clapboard. Double or triple windows should have a 4" to 6" mullion in between.
Brick molding is required around doors, windows, and vents within masonry walls but is not appropriate on non-masonry clad buildings.

b. Garages, if visible from the street, should be situated on the lot as historically traditional for the neighborhood.

Generally new garages should be placed close to the alley, at the rear of the lot, or in the original location of an historic accessory structure.

Lots without rear alleys may have garages located closer to the primary structure. The appropriate location is one that matches the neighborhood or can be documented by historic maps.

Generally, attached garages are not appropriate; however, instances where they may be are:

- Where they are a typical feature of the neighborhood; or*
- When the location of the attached garage is in the general location of an historic accessory building, the new garage is located in the basement level, and the vehicular access is on the rear elevation.*

Setbacks & Site Requirements.

· To reflect the character of historic outbuildings, new outbuildings for duplexes should not exceed the requirements for outbuildings for the entire lot and should not be doubled. The most appropriate configurations would be two 1-bay buildings with or without parking pads for additional spaces or one 2-bay building.
· A DADU or outbuilding may only be located behind the principal structure in the established rear yard. The DADU or outbuilding is to be subordinate to the principal structure and therefore should be placed to the rear of the lot.

- There should be a minimum separation of 20' between the principal structure and the DADU or outbuilding.
- At least one side setback for a DADU or outbuilding on an interior lot, should generally be similar to the principle dwelling but no closer than 3' from each property line. The rear setback may be up to 3' from the rear property line. For corner lots, the DADU or outbuilding should match the context of homes on the street. If there is no context, the street setback should be a minimum of 10'.

Driveway Access.

- On lots with no alley access, the lot shall have no more than one curb-cut from any public street for driveway access to the principal structure as well as the detached accessory dwelling or outbuilding.
- On lots with alley access, any additional access shall be from the alley and no new curb cuts shall be provided from public streets.
- Parking accessed from any public street shall be limited to one driveway for the lot with a maximum width of twelve feet.

Additional Requirements for DADUs from Ordinance 17.16.030. See requirements for outbuildings for additional requirements.

- The lot area on which a DADU is placed shall comply with Table 17.12.020A.
- The DADU may not exceed the maximums outlined previously for outbuildings.
- No additional accessory structure shall exceed two hundred square feet when there is a DADU on the lot.

Density.

- A DADU is not allowed if the maximum number of dwelling units permitted for the lot has been met.

Ownership.

- a. No more than one DADU shall be permitted on a single lot in conjunction with the principal structure.
- The DADU cannot be divided from the property ownership of the principal dwelling.
- The DADU shall be owned by the same person as the principal structure and one of the two dwellings shall be owner-occupied.
- Prior to the issuance of a permit, an instrument shall be prepared and recorded with the register's office covenanting that the DADU is being established accessory to a principal structure and may only be used under the conditions listed here.

Bulk and Massing.

- The living space of a DADU shall not exceed seven hundred square feet.

- c. The location and design of outbuildings should not be visually disruptive to the character of the surrounding buildings.

9. Appurtenances

Appurtenances related to new buildings, including driveways, sidewalks, lighting, fences, and walls, shall be visually compatible with the environment of the existing buildings and sites to which they relate.

Utilities

Utility connections such as gas meters, electric meters, phone, cable, and HVAC condenser units should be located so as to minimize their visibility from the street.

Generally, utility connections should be placed no closer to the street than the mid point of the structure.

Power lines should be placed underground if they are carried from the street and not from the rear or an alley.

Public Spaces

Landscaping, sidewalks, signage, lighting, street furniture and other work undertaken in public spaces by any individual, group or agency shall be presented to the MHZC for review of compatibility with the character of the district.

Generally, mailboxes should be attached to the front wall of the house or a porch post. In most cases, street-side mailboxes are inappropriate.

10. ADDITIONS

- a. Generally, an addition should be situated at the rear of a building in such a way that it will not disturb either front or side facades.

Placement

Additions should be located at the rear of an existing structure.

Connections to additions should, as much as possible, use existing window and door openings rather than remove significant amounts of rear wall material.

Generally, one-story rear additions should inset one foot, for each story, from the side wall.

Additions should be physically distinguished from the historic building and generally fit within the shadow line of the existing building.

Additions that tie-into the existing roof must be at least 6" below the existing ridge line.

In order to assure that an addition has achieved proper scale, the addition should:

- No matter its use, an addition should not be larger than the existing house, not including non-historic additions, in order to achieve compatibility in scale. This will allow for the retention of small and medium size homes in the neighborhood. The diversity of housing type and size is a character defining feature of the historic districts.*
- Additions which are essentially a house-behind-a-house with a long narrow connector are not appropriate, as the form does not exist historically. Short or minimal connections that do not require the removal of the entire back wall of a historic building are preferred.*
- Additions should generally be shorter and thinner than the existing building. Exceptions may be made when unusual constraints make these parameters unreasonable, such as:*
 - An extreme grade change*
 - Atypical lot parcel shape or size*

In these cases, an addition may rise above or extend wider than the existing building; however, generally the addition should not be taller and extend wider.

When an addition needs to be taller:

Whenever possible, additions should not be taller than the historic building; however, when a taller addition is the only option, additions to single story structures may rise as high as 4' above the shadow line of the existing building at a distance of 40' from the front edge of the existing building.

In this instance, the side walls and roof of the addition must set in as is typical for all additions.

The portion of the roof that can be seen should have a hipped, side gable or clipped gable roof to help decrease the visual mass of the addition.

When an addition needs to be wider:

Rear additions that are wider than an existing historic building may be appropriate when the building is narrower than 30' or shifted to one side of the lot. In these instances, a structural alcove or channel must separate the existing building from the new addition. The structural alcove should sit in a minimum of 1' and be at least twice as long as it is deep.

In addition, a rear addition that is wider should not wrap the rear corner.

Ridge raises

Ridge raises are most appropriate for one-story, side-gable buildings, (without clipped gables) and that require more finished height in the attic. The purpose of a ridge raise is to allow for conditioned space in the attic and to discourage large rear or side additions. The raised portion must sit in a minimum of 2' from each side wall and can be raised no more than 2' of total vertical height

within the same plane as the front roof slope.

Sunrooms

Metal framed sunrooms, as a modern interpretation of early green houses, are appropriate if they are mostly glass or use appropriate cladding material for the district, are located at the rear in a minimally visible location, are minimally attached to the existing structure, and follow all other design guidelines for additions.

Foundation

Foundation walls should set in from the existing foundation at the back edge of the existing structure by one foot for each story or half story. Exception: When an addition is a small one-room deep (12' deep or less) addition that spans the width of the structure, and the existing structure is masonry with the addition to be wood (or appropriate substitute siding). The change in material from masonry to wood allows for a minimum of a four inch (4") inset.

Foundation height should match or be lower than the existing structure.

Foundation lines should be visually distinct from the predominant exterior wall material. This is generally accomplished with a change in materials.

Roof

The height of the addition's roof and eaves must be less than or equal to the existing structure.

Visually evident roof slopes should match the roof slopes of the existing structure, and roof planes should set in accordingly for rear additions.

Skylights should not be located on the front-facing slope of the roof. Skylights should be flat (no bubble lenses) with a low profile (no more than six inches tall) and only be installed behind the midpoint of the building).

Dormer additions are appropriate for some historic buildings as they are a traditional way of adding ventilation and light to upper stories.

The addition of a dormer that would require the removal of historic features such as an existing dormer, chimneys, cupolas or decorative feature is not appropriate.

Rear dormers should be inset from the side walls of the building by a minimum of two feet. The top of a rear dormer may attach just below the ridge of the main roof or lower.

Side dormers should be compatible with the scale and design of the building. Generally, this can be accomplished with the following:

- New dormers should be similar in design and scale to an existing dormer on the building.*
- New dormers should be similar in design and scale to an existing dormer on another historic building that is similar in style and massing.*
- The number of dormers and their location and size should be appropriate to the style and design of the building. Sometimes dormer locations relate to the openings below. The symmetry or lack of symmetry within a building design should be used as a guide when placing dormers.*
- Dormers should not be added to secondary roof planes.*
- Eave depth on a dormer should not exceed the eave depth on the main roof.*
- The roof form of the dormer should match the roof form of the building or be appropriate for the style.*
- The roof pitch of the dormer should generally match the roof pitch of the building.*
- The ridge of a side dormer should be at least 2' below the ridge of the existing building; the cheeks should be inset at least 2' from the wall below or adjacent valley; and the front wall of the gable should setback a minimum of 2' from the wall below. (These minimum insets will likely be greater than 2' when following the guidelines for appropriate scale.)*
- Dormers should generally be fully glazed and aprons below the window should be minimal.*
- The exterior material cladding of side dormers should match the primary or secondary material of the main building.*

Side Additions

When a lot width exceeds 60' or the standard lot width on the block, it may be appropriate to add a side

addition to a historic structure. The addition should set back from the face of the historic structure (at or beyond the midpoint of the building) and should be subservient in height, width and massing to the historic structure.

Side additions should be narrower than half of the historic building width and exhibit a height of at least 2' shorter than the historic building.

To deemphasize a side addition, the roofing form should generally be a hip or side-gable roof form.

Commercial buildings that desire a covered open-air side additions generally should not enclose the area with plastic sides. Such applications may be appropriate if: the addition is located on the ground level off a secondary facade, is not located on a street facing side of a building, has a permanent glass wall on the portion of the addition which faces the street, and the front sits back a minimum of three (3') from the front or side wall, depending on placement of the addition.

b. The creation of an addition through enclosure of a front porch is not appropriate.

Side porch additions may be appropriate for corner building lots or lots more than 60' wide.

c. Contemporary designs for additions to existing properties are not discouraged when such additions do not destroy significant historical, architectural, or cultural material; and when such design is compatible, by not contrasting greatly, with the size, scale, color, material, and character of the property, neighborhood, or environment.

d. A new addition should be constructed in such a manner that if the addition were to be removed in the future, the essential form and integrity of the original structure would be unimpaired.

Connections should, as much as possible, use existing window and door openings rather than remove significant amounts of rear wall material.

e. Additions should follow the guidelines for new construction.

III.B. Demolition

1. Demolition is not appropriate

a. if a building, or major portion of a building, is of such architectural or historical interest and value that its removal would be detrimental to the public interest; or

b. if a building, or major portion of a building, is of such old or unusual or uncommon design and materials that it could not be reproduced or be reproduced without great difficulty and expense.

2. Demolition is appropriate

a. if a building, or major portion of a building, has irretrievably lost its architectural and historical integrity and significance and its removal will result in a more historically appropriate visual effect on the district;

b. if a building, or major portion of a building, does not contribute to the historical and architectural character and significance of the district and its removal will result in a more historically appropriate visual effect on the district; or

c. if the denial of the demolition will result in an economic hardship on the applicant as determined by the MHZC in accordance with section 17.40.420 (Historic Zoning Regulations), Metropolitan Comprehensive Zoning Ordinance.

Background: 1510 Holly is a pre-1908 folk Victorian house that contributes to the historic character of the Lockeland Springs-East End Neighborhood Conservation Zoning Overlay (Figure 1). The house was damaged during the March 3, 2020, tornado. The historic house was damaged but can be repaired. The outbuilding at the rear, which was constructed in 2005, was destroyed by the tornado.



Figure 1. 1510 Holly Street after the March 3, 2020 tornado.



Figure 2. Tornado damage



Figure 3. Rear façade tornado damage.



Figure 4. Remnants of the two-story garage after the tornado

Analysis and Findings: The applicant proposes a rear addition and a new outbuilding (Detached Accessory Dwelling Unit). 1510 Holly sustained damage in the March 3, 2020 tornado, and its existing garage was demolished during the storm.

Demolition: The rear addition requires the removal of an existing appendage at the rear (Figure 5). The date of construction of this part of the house is not known; it appears in the 1951 Sanborn map as a porch but not on the 1914 Sanborn Map (Figures 6 & 7). Staff finds that this part of the house is not historically or architecturally significant, as it is not original, and that its removal meets the design guidelines.

Staff finds that the proposed partial demolition meets Section III.B.2 for appropriate demolition and does not meet Section III.B.1 for inappropriate demolition.




Figure 5 (left) is the area to be removed. Figure 6 (center) is the 1914 Sanborn map where this part of the house does not appear and Figure 7 (right) is the 1951 Sanborn map where it appears as a porch.

Height & Scale: The proposed addition is one-story in height and about eighteen inches (18") lower in height than the historic house. Its eave and foundation heights will match those of the historic house. The addition is inset one foot (1') from each of the back corners of the house for its entire depth, which meets the design guidelines. The addition has a footprint of one thousand, three hundred and twenty square feet (1,320 sq. ft.), as compared to the historic house which has a footprint of about one thousand, nine hundred and fifty-one square feet (1,951 sq. ft.). Overall, staff finds that the addition's height and scale are compatible with the historic house and meets the design guidelines.

Staff finds that the proposed addition's height and scale meet Sections II.B.1., II.B.2., and II.B.10. of the design guidelines.

Location & Removability: The addition is located entirely at the rear of the house, is inset one foot (1') from the back corners of the house, and has a separate roof form. For all these reasons, it could be removed in the future without affecting the historic house's architectural integrity.

Staff finds that the proposed addition meets Sections II.B.2.a and II.B.2.d. of the design guidelines.

Design: The location of the addition at the rear of the existing building is in accordance with the design guidelines. The addition's change in materials, inset, separate roof form, and lower height help to distinguish it from the historic house and read as an addition to the house. At the same time, its scale, materials, roof form, and fenestration pattern are all compatible with the historic character of the existing house. The addition is designed so that if the addition were to be removed in the future, the historic character of the house would still be intact.

Staff finds that the addition's design meets Sections II.B.2.a and II.B.2.e. of the design guidelines.

Setback & Rhythm of Spacing: The proposed addition meets all base zoning setbacks. It is six feet (6') from the right-side property line, approximately eleven feet (11') from the left side property line, and forty-four feet (44') from the rear property line. There is twenty feet (20') between the back of the addition and the proposed outbuilding, which meets the design guidelines.

Staff finds that the proposed setbacks meet Sections II.B.3. and II.B.10. of the design guidelines.

Materials:

	Proposed	Color/Texture/ Make/Manufacturer	Approved Previously or Typical of Neighborhood	Requires Additional Review
Foundation	Brick	Unknown	Yes	Yes
Cladding	4" cement fiberboard lap siding	Smooth*	Yes	No
Roofing	Architectural Shingles	Match existing (grey)	Yes	No
Trim	Cement Fiberboard or Wood	Smooth faced	Yes	No

Rear Porch floor/steps	Wood	Typical	Yes	No
Rear Porch Posts	Wood	Typical	Yes	No
Rear Porch Railing	Wood	Typical	Yes	No
Windows	Aluminum Clad	Ply Gem Mira	Yes	No
Rear Door	Steel	Full Glass	Yes	No
Front Door	Fiberglass	Full Glass	Yes	No
Driveway	Not indicated	Needs final approval	Unknown	Yes

With staff’s approval of all final material choices, including a brick sample, Staff finds that the materials meet Sections II.B.4. and II.B.10 of the design guidelines.

Roof form: The addition’s roof form preserves the multi-faceted roof form of this Folk Victorian house. It has a mixture of gable and shed forms with 9/12 and 3/12 slopes. Staff finds that these roof forms are compatible with the historic house, particularly because they help to preserve the historic house’s roof form.

Staff finds that the proposed roof forms meet Sections II.B.5. and II.B.10. of the design guidelines.

Proportion and Rhythm of Openings: No changes to the window and door openings on the existing house were indicated on the plans. The windows on the proposed addition are all generally twice as tall as they are wide, thereby meeting the historic proportions of openings. There are no large expanses of wall space without a window or door opening.

Staff finds the project’s proportion and rhythm of openings to meet Sections II.B.7. and II.B.10.

Appurtenances & Utilities: No changes to the site’s appurtenances were indicated on the drawings. The location of the HVAC and other utilities was also not noted. Staff recommends that the HVAC be located on the rear façade, or on a side façade beyond the midpoint of the house.

Outbuildings: Staff is proposing a two-story outbuilding. Typically, MHZC staff would limit any outbuilding here to a one or one-and-one-half story structure. However, the outbuilding that was destroyed in the 2020 tornado was two stories and had been approved by MHZC in 2005 (Figure 5).




Figure 5. The alley façade of the garage that MHZC approved in 2005, but which was demolished by the March 2020 tornado.

The project meets section II.B.8 of the design guidelines and ordinance 17.16.030.G for detached accessory dwelling units.

The project meets section II.B.8 of the design guidelines.

Massing Planning:

	Potential maximums (heights to be measured from grade)	Existing conditions (height of historic portion of the home to be measured from finished floor)	Proposed
Ridge Height	25' unless existing building is less	27'	24' 3"
Eave Height	10'	11'	9'-8"

The lot is eight thousand, five hundred and ninety-three square feet (8,593 sq. ft.), less than 10,000 square feet, therefore the maximum footprint allowed is seven hundred and fifty square feet (750 sq. ft.).

Proposed	50% of first floor area of principle structure	Lot is less than 10,000 square feet	Proposed
Maximum Square Footage	1131 sq. ft.	750 sq. ft. (including porches)	696 sq. ft.

The project meets Section II.B.8 of the design guidelines and 17.16.30.G. 7 of the ordinance for height and scale.

Site Planning & Setbacks:

	MINIMUM	PROPOSED
Building located towards rear of lot	n/a	Yes
Space between principal building and DADU/Garage	20'	24'-4"
Rear setback***	3'	5'
L side setback**	3'	26'
R side setback**	3'	5'
How is the building accessed?	From the alley or existing curb cut	Existing driveway

**Since the proposed footprint of the outbuilding is less than seven hundred square feet (700 sq. ft.), the minimum side setbacks are three feet (3').

***Since the footprint of the outbuilding is less than seven hundred square feet (700 sq. ft.) and the garage doors do not face an alley, the rear setback is three feet (3').

Staff finds that the proposed outbuilding meets Section II.B.8 of the design guidelines and 17.16.30.G. 4 of the ordinance.

Roof Shape:

Proposed Element	Proposed Form	Typical of district?
Primary form	Side gable	Yes
Primary roof slope	12/12	Yes
Dormer form	Shed	Yes
Dormer roof slope	3/12	Yes

Since the roof form and slopes are similar to historic outbuildings, the project meets Section II.B.8.a of the design guidelines and Section 17.16.030.G.8 of the ordinance.

Design Standards:

The proposed outbuilding has a simple design that is subordinate to the primary structure and appropriate for outbuildings. The design meets Section II.B.8.a of the design guidelines and Section 17.16.030.G.8 of the ordinance.

Materials:

	Proposed	Color/Texture	Approved Previously or Typical of Neighborhood	Requires Additional Review?
Foundation	Concrete slab	Natural	Yes	No
Cladding	Fiber-cement siding, 5" reveal	Smooth	Yes	No
Secondary cladding	Board-and-batten	Smooth	Yes	No
Roofing	Asphalt shingle	Match house's roof (Grey)	Yes	No
Trim	Fiber-cement or wood	Smooth	Yes	No
Windows	Ply Gem Mira	Aluminum Clad	Yes	No
Doors	Steel	Typical	Yes	No
Garage door	Insulated metal	Needs final approval	Yes	Yes

With the staff's final approval of the garage doors, staff finds that the known materials meet Section II.B.8.a.

General requirements for DADUs:

The answer to each of these questions must be "yes" for either an outbuilding or a DADU.

	YES	NO
If there are stairs, are they enclosed?	YES	
If a corner lot, are the design and materials similar to the principal building?	n/a	
If dormers are used, do they cover less than 50% of the roof plane where they are located as measured from side-to-side?	YES	
If dormers are used, do they sit back from the wall below by at least 2'?	YES	
Is the roof pitch at least 4/12?	YES	

If the building is two-bay and the vehicular doors face the street, are there two different doors rather than one large door?	n/a	
Is the building located towards the rear of the lot?	YES	

The project meets Section II.B.8.a of the design guidelines and sections 17.16.30.G.5, 8 and 9 of the ordinance.

General Requirements for DADU:


The answer to each of these questions must be “no.”

	YES	NO
Does the lot NOT comply with Table 17.12.020A of the zoning code? (It isn't zoned two-family or doesn't have adequate square footage to be a legally conforming lot.)		NO
Are there other accessory buildings on the lot that exceed 200 square feet?		NO
Is the property zoned single-family?		NO
Are there already two units on the property?		NO
Does the property owner NOT live on site or does NOT plan to move to this location once the DADU is complete?		NO
Is the planned conditioned living space more than 700 square feet?		NO

The project meets Section II.B.8.a of the design guidelines and sections 17.16.30.G.1,2,3, and 7 of the ordinance.

Recommendation Summary: Staff recommends approval of the project with the condition that staff approve a brick sample, the garage door, and the HVAC location prior to purchase and installation. With these conditions, staff finds that the proposed addition and DADU meet Sections II.B. and III.B. of the design guidelines and 17.16.030.G, the DADU ordinance.

EXISTING CONDITIONS



It is the responsibility of the owner and/or contractor to verify that the plans meet any and all codes in the area in which the structure will be built prior to construction.

Owner and/or contractor to verify all dimensions prior to beginning construction.

All structural components to be verified by supplier and/or engineer prior to beginning construction.

Revisions
Drafter J. Kurkimilis
Date
Scale
Sheet Name
Sheet


PROPOSED ADDITION/DADU

It is the responsibility of the owner and/or contractor to verify that the plans meet any and all codes in the area in which the structure will be built prior to construction.

Owner and/or contractor to verify all dimensions prior to beginning construction.


All structural components to be verified by supplier and/or engineer prior to beginning construction.

Revisions
Drafter J. Kurkimilis
Date
Scale
Sheet Name
Sheet



THESE ARCHITECTURAL PLANS ARE PROTECTED BY COPYRIGHT LAW. THE REPRODUCTION OR UNAUTHORIZED USE IS STRICTLY PROHIBITED. THOSE IN VIOLATION WILL BE PURSUED TO THE FULLEST EXTENT UNDER THE LAW INCLUDING BUT NOT LIMITED TO DAMAGES AND RELATED ATTORNEY FEES.

DEMO PLAN



1 FLOOR 1 COPY 1
1/4" = 1'-0"



1510 HOLLY ST
NASHVILLE, TN

IT IS THE RESPONSIBILITY OF THE OWNER AND/OR CONTRACTOR TO VERIFY THAT THE PLANS MEET ANY AND ALL CODES IN THE AREA IN WHICH THE STRUCTURE WILL BE BUILT PRIOR TO CONSTRUCTION. OWNER AND/OR CONTRACTOR TO VERIFY ALL DIMENSIONS PRIOR TO BEGINNING CONSTRUCTION. ALL STRUCTURAL COMPONENTS TO BE VERIFIED BY SUPPLIER AND/OR ENGINEER PRIOR TO BEGINNING CONSTRUCTION. CONTRACTOR SHALL VERIFY SITE AND REPORT ANY CONDITIONS THAT MAY CONFLICT WITH DESIGN TO DESIGNER. CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR ANY DISCREPANCIES NOT REPORTED.

No.	Revision Description	Date
1	Initial Concept	11/4/19


FLOOR PLANS

DRAWING STATUS: PRELIMINARY
DATE: 5/5/20
DRAWN BY: J. KURKIMILIS

A1.3

THESE ARCHITECTURAL PLANS ARE PROTECTED BY COPYRIGHT LAW. THE REPRODUCTION OR UNAUTHORIZED USE IS STRICTLY PROHIBITED. THOSE IN VIOLATION WILL BE FORSUED TO THE FULLEST EXTENT UNDER THE LAW INCLUDING BUT NOT LIMITED TO DAMAGES AND RELATED ATTORNEY FEES.

1. THE CONTRACTOR SHALL CONFORM TO ALL APPLICABLE RULES, REGULATIONS AND CODES, OBTAIN ALL NECESSARY PERMITS, PAY ALL FEES AND GIVE ALL NOTICES REQUIRED FOR EXECUTION OF THE WORK PRIOR TO BEGINNING THE WORK.
2. THE LOCATION AND SIZE OF EXISTING UTILITIES SHOWN ON THESE CONSTRUCTION PLANS IS APPROXIMATE ONLY. OTHER UTILITIES MAY EXIST AND MAY NOT BE SHOWN, OR MAY VARY FROM LOCATIONS SHOWN. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION AND SIZE OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK AND SHALL BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO VERIFY LOCATION AND SIZE OF ANY AND ALL UNDERGROUND OR OVERHEAD UTILITIES. NO GUARANTEES ARE EXPRESSED OR IMPLIED WITH RESPECT TO UTILITY LOCATIONS AND SIZES SHOWN HEREIN.
3. IN THE EVENT OF ANY DISCREPANCIES AND/OR ERRORS FOUND IN THE CONSTRUCTION PLANS, OR IF PROBLEMS ARE ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL BE REQUIRED TO NOTIFY DESIGNER BEFORE PROCEEDING WITH THE WORK. IF DESIGNER IS NOT NOTIFIED, THE CONTRACTOR SHALL ASSUME AND TAKE RESPONSIBILITY FOR THE COST OF ANY REVISION AND ANY OTHER DAMAGES OR COSTS STEMMING THEREFROM.
4. PRIOR TO BEGINNING WORK, THE CONTRACTOR SHALL VERIFY THAT ACTUAL SITE CONDITIONS (INCLUDING, BUT NOT LIMITED TO, ELEVATIONS, GRADES AND DIMENSIONS) ARE CONSISTENT WITH THE EXISTING CONDITIONS DEPICTED ON THESE CONSTRUCTION PLANS. IN THE EVENT OF ANY DISCREPANCIES AND/OR ERRORS ARE FOUND IN THE CONSTRUCTION PLANS, OR IF PROBLEMS ARE ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL TO NOTIFY THE DESIGNER AND OWNER BEFORE PROCEEDING WITH THE WORK. COMMENCEMENT OF CONSTRUCTION BY THE CONTRACTOR SHALL INDICATE THAT THE CONTRACTOR ACCEPTS THE ACTUAL SITE CONDITIONS AS MATCHING EXISTING CONDITIONS DEPICTED ON THE CONSTRUCTION PLANS.
5. PRIOR TO BEGINNING WORK, THE CONTRACTOR SHALL VERIFY ANY AND ALL DIMENSIONS, WIDTHS, HEIGHTS, SQUARE FOOTAGES, AND ANY OTHER CALCULATIONS DEPICTED ON THESE CONSTRUCTION PLANS. NO GUARANTEES ARE EXPRESSED OR IMPLIED WITH RESPECT TO SQUARE FOOTAGES REPRESENTED ON THESE CONSTRUCTION PLANS.
6. SUBSURFACE AND ENVIRONMENTAL CONDITIONS WERE NOT EXAMINED OR CONSIDERED DURING THE PREPARATION OF THESE CONSTRUCTION PLANS AND NO REPRESENTATION IS MADE CONCERNING THE EXISTENCE OF UNDERGROUND CONTAINERS, FACILITIES, WELLS, SINK HOLES, GRAVE SITES, DEBRIS OR ANY OTHER SUBSURFACE CONDITION THAT MAY AFFECT THE USE OR DEVELOPMENT OF THIS PROJECT.
7. THE DESIGNER DOES NOT GUARANTEE THE SUITABILITY OF THE SUBSURFACE CONDITIONS FOR THE WORK INDICATED. DETERMINATION OF THE SUITABILITY OF SUBSURFACE CONDITIONS FOR THE WORK INDICATED IS SOLELY THE RESPONSIBILITY OF THE OWNER AND/OR CONTRACTOR.
8. THE DESIGNER DOES NOT GUARANTEE THE WORK OF ANY CONTRACTOR OR SUBCONTRACTOR. SHALL HAVE NO AUTHORITY TO STOP WORK, SHALL HAVE NO AUTHORITY TO DIRECT WORK, SHALL NOT BE RESPONSIBLE FOR JOB SITE SAFETY, OR HAVE ANY CONTROL OVER JOB SITE SAFETY.
9. THE CONTRACTOR IS RESPONSIBLE FOR ALL DEMOLITION AND REMOVAL NECESSARY TO ACCOMPLISH THE PROPOSED IMPROVEMENTS SHOWN ON THESE CONSTRUCTION PLANS.
10. THE CONTRACTOR SHALL VERIFY THAT THERE ARE NO CONFLICTS WITH EXISTING OR PROPOSED UNDERGROUND OR OVERHEAD UTILITY LINES OR EASEMENTS.
11. THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH THE TENNESSEE UNDERGROUND UTILITY DAMAGE PREVENTION ACT (ONE-CALL) AND FOR ESTABLISHING THE EXACT VERTICAL AND HORIZONTAL LOCATION OF EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR SHALL COORDINATE ALL CONSTRUCTION WITH THE APPROPRIATE UTILITY COMPANY. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS. THE CONTRACTOR SHALL PERFORM ALL WORK IN A MANNER THAT WILL NOT CAUSE DAMAGE TO EXISTING UTILITIES THAT ARE TO REMAIN. TO THE EXTENT ANY EXISTING UTILITIES ARE DAMAGED, CONTRACTOR SHALL REPAIR ALL DAMAGE ACCORDING TO LOCAL STANDARDS AT THE CONTRACTOR'S EXPENSE. DESIGNER IS NOT RESPONSIBLE FOR ANY DAMAGES AS A RESULT OF CONTRACTOR'S FAILURE TO COORDINATE UTILITY WORK.
12. NECESSARY AND SUFFICIENT BARRICADES, LIGHTS, SIGNS, AND OTHER TRAFFIC CONTROL MEASURES, AS MAY BE NECESSARY FOR THE PROTECTION AND SAFETY OF THE PUBLIC SHALL BE PROVIDED AND MAINTAINED THROUGHOUT THE CONSTRUCTION PERIOD.
13. THE CONTRACTOR SHALL ENSURE COMPLIANCE WITH ALL APPLICABLE RULES, REGULATIONS, AND CODES WITH RESPECT TO STORM WATER DISCHARGES, OR SEDIMENT OR EROSION CONTROL THROUGHOUT CONSTRUCTION. THE GRADING CONTRACTOR SHALL USE WHATEVER MEASURES ARE REQUIRED TO PREVENT SILT AND CONSTRUCTION DEBRIS FROM FLOWING ONTO ADJACENT PROPERTIES. THE CONTRACTOR SHALL COMPLY WITH ALL LOCAL EROSION, CONSERVATION AND SILTATION ORDINANCES.
14. THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO OR CONCURRENT WITH LAND DISTURBING ACTIVITIES. THE DESIGNER IS NOT RESPONSIBLE FOR ANY EROSION OR SEDIMENT PROBLEMS ENCOUNTERED DURING CONSTRUCTION.



SHEET LIST	
SHEET NAME	SHEET NUMBER
COVER SHEET	A0
FOUNDATION/ROOF	A1.0
FLOOR PLANS	A1.2
FRONT ELEVATION	A2.0
SIDE ELEVATIONS	A2.2
SECTIONS	A3.0
PERSPECTIVES	A6.0
PERSPECTIVES	A6.1

PROJECT SUMMARY

LEGACY SOUTH BUILDERS 615.861.1669 2012 RESIDENTIAL BUILDING CODE

BEDROOMS	4	WIDTH	31'-1"
FULL BATHS	3	DEPTH	9'-1"
HALF BATHS	1	HEIGHT	29'-7 19/32"

HEATED/COOLED	
LEVEL	AREA
FLOOR 1	2411 SF
GRAND TOTAL: 1	2411 SF

PORCHES/DECKS	
AREA	COMMENTS
321 SF	NEW DECK
321 SF	



1510 HOLLY ST
NASHVILLE, TN

No.	Revision Description	Date
1	Initial Concept	5/5/20
2	First revisions from Historic review	7/20/20

COVER SHEET


DRAWING STATUS: PRELIMINARY
DATE: 5/5/20
DRAWN BY: J. KURKIMILIS

A0


IT IS THE RESPONSIBILITY OF THE OWNER AND/OR CONTRACTOR TO VERIFY THAT THE PLANS MEET ANY AND ALL CODES IN THE AREA IN WHICH THE STRUCTURE WILL BE BUILT PRIOR TO CONSTRUCTION. OWNER AND/OR CONTRACTOR TO VERIFY ALL DIMENSIONS PRIOR TO BEGINNING CONSTRUCTION. ALL STRUCTURAL COMPONENTS TO BE VERIFIED BY SUPPLIER AND/OR ENGINEER PRIOR TO BEGINNING CONSTRUCTION. CONTRACTOR SHALL VERIFY SITE AND REPORT ANY CONDITIONS THAT MAY CONFLICT WITH DESIGN TO DESIGNER. CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR ANY DISCREPANCIES NOT REPORTED.

THESE ARCHITECTURAL PLANS ARE PROTECTED BY COPYRIGHT LAW. THE REPRODUCTION OR UNAUTHORIZED USE IS STRICTLY PROHIBITED. THOSE IN VIOLATION WILL BE FORSUED TO THE FULLEST EXTENT UNDER THE LAW INCLUDING BUT NOT LIMITED TO DAMAGES AND RELATED ATTORNEY FEES.

1 TOP FOUNDATION
3/16" = 1'-0"



2 RIDGE HEIGHT
3/16" = 1'-0"



1510 HOLLY ST
NASHVILLE, TN

IT IS THE RESPONSIBILITY OF THE OWNER AND/OR CONTRACTOR TO VERIFY THAT THE PLANS MEET ANY AND ALL CODES IN THE AREA IN WHICH THE STRUCTURE WILL BE BUILT PRIOR TO CONSTRUCTION. OWNER AND/OR CONTRACTOR TO VERIFY ALL DIMENSIONS PRIOR TO BEGINNING CONSTRUCTION. ALL STRUCTURAL COMPONENTS TO BE VERIFIED BY SUPPLIER AND/OR ENGINEER PRIOR TO BEGINNING CONSTRUCTION. CONTRACTOR SHALL VERIFY SITE AND REPORT ANY CONDITIONS THAT MAY CONFLICT WITH DESIGN TO DESIGNER. CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR ANY DISCREPANCIES NOT REPORTED.

No.	Revision Description	Date
1	Initial Concept	5/5/20

FOUNDATION/ROOF


DRAWING STATUS: PRELIMINARY
DATE: 5/5/20
DRAWN BY: J. KURKIMILIS

AI.0

THESE ARCHITECTURAL PLANS ARE PROTECTED BY COPYRIGHT LAW. THE REPRODUCTION OR UNAUTHORIZED USE IS STRICTLY PROHIBITED. THOSE IN VIOLATION WILL BE PURSUED TO THE FULLEST EXTENT UNDER THE LAW INCLUDING BUT NOT LIMITED TO DAMAGES AND RELATED ATTORNEY FEES.



1 FRONT 1/4" = 1'-0"



2 REAR 1/4" = 1'-0"

1510 HOLLY ST
 NASHVILLE, TN


IT IS THE RESPONSIBILITY OF THE OWNER AND/OR CONTRACTOR TO VERIFY THAT THE PLANS MEET ANY AND ALL CODES IN THE AREA IN WHICH THE STRUCTURE WILL BE BUILT PRIOR TO CONSTRUCTION. OWNER AND/OR CONTRACTOR TO VERIFY ALL DIMENSIONS PRIOR TO BEGINNING CONSTRUCTION. ALL STRUCTURAL COMPONENTS TO BE VERIFIED BY SUPPLIER AND/OR ENGINEER PRIOR TO BEGINNING CONSTRUCTION. CONTRACTOR SHALL VERIFY SITE AND REPORT ANY CONDITIONS THAT MAY CONFLICT WITH DESIGN TO DESIGNER. CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR ANY DISCREPANCIES NOT REPORTED.

No.	Revision Description	Date
1	Initial Concept	5/5/20


FRONT ELEVATION

DRAWING STATUS PRELIMINARY
 DATE 5/5/20
 DRAWN BY J. KURKIMILIS

THESE ARCHITECTURAL PLANS ARE PROTECTED BY COPYRIGHT LAW. THE REPRODUCTION OR UNAUTHORIZED USE IS STRICTLY PROHIBITED. THOSE IN VIOLATION WILL BE PROSECUTED TO THE FULLEST EXTENT UNDER THE LAW INCLUDING BUT NOT LIMITED TO DAMAGES AND RELATED ATTORNEY FEES.



① LEFT
3/16" = 1'-0"



② RIGHT
3/16" = 1'-0"

1510 HOLLY ST
NASHVILLE, TN



IT IS THE RESPONSIBILITY OF THE OWNER AND/OR CONTRACTOR TO VERIFY THAT THE PLANS MEET ANY AND ALL CODES IN THE AREA IN WHICH THE STRUCTURE WILL BE BUILT PRIOR TO CONSTRUCTION. OWNER AND/OR CONTRACTOR TO VERIFY ALL DIMENSIONS PRIOR TO BEGINNING CONSTRUCTION. ALL STRUCTURAL COMPONENTS TO BE VERIFIED BY SUPPLIER AND/OR ENGINEER PRIOR TO BEGINNING CONSTRUCTION. CONTRACTOR SHALL VERIFY SITE AND REPORT ANY CONDITIONS THAT MAY CONFLICT WITH DESIGN TO DESIGNER. CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR ANY DISCREPANCIES NOT REPORTED.

No.	Revision Description	Date
1	Initial Concept	5/5/20

SIDE ELEVATIONS

DRAWING STATUS: PRELIMINARY
 DATE: 5/5/20
 DRAWN BY: J. KURKIMILIS

THESE ARCHITECTURAL PLANS ARE PROTECTED BY COPYRIGHT LAW. THE REPRODUCTION OR UNAUTHORIZED USE IS STRICTLY PROHIBITED. THOSE IN VIOLATION WILL BE PURSUED TO THE FULLEST EXTENT UNDER THE LAW INCLUDING BUT NOT LIMITED TO DAMAGES AND RELATED ATTORNEY FEES.



**1510 HOLLY ST
NASHVILLE, TN**

IT IS THE RESPONSIBILITY OF THE OWNER AND/OR CONTRACTOR TO VERIFY THAT THE PLANS MEET ANY AND ALL CODES IN THE AREA IN WHICH THE STRUCTURE WILL BE BUILT PRIOR TO CONSTRUCTION.
OWNER AND/OR CONTRACTOR TO VERIFY ALL DIMENSIONS PRIOR TO BEGINNING CONSTRUCTION.
ALL STRUCTURAL COMPONENTS TO BE VERIFIED BY SUPPLIER AND/OR ENGINEER PRIOR TO BEGINNING CONSTRUCTION.
CONTRACTOR SHALL VERIFY SITE AND REPORT ANY CONDITIONS THAT MAY CONFLICT WITH DESIGN TO DESIGNER.
CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR ANY DISCREPANCIES NOT REPORTED.

No.	Revision Description	Date
1	Initial Concept	5/5/20


PERSPECTIVES

DRAWING STATUS PRELIMINARY
DATE 5/5/20
DRAWN BY J. KURKIMILIS

A6.0

THESE ARCHITECTURAL PLANS ARE PROTECTED BY COPYRIGHT LAW. THE REPRODUCTION OR UNAUTHORIZED USE IS STRICTLY PROHIBITED. THOSE IN VIOLATION WILL BE PURSUED TO THE FULLEST EXTENT UNDER THE LAW INCLUDING BUT NOT LIMITED TO DAMAGES AND RELATED ATTORNEY FEES.

1. THE CONTRACTOR SHALL CONFORM TO ALL APPLICABLE RULES, REGULATIONS AND CODES, OBTAIN ALL NECESSARY PERMITS, PAY ALL FEES AND GIVE ALL NOTICES REQUIRED FOR EXECUTION OF THE WORK PRIOR TO BEGINNING THE WORK.
2. THE LOCATION AND SIZE OF EXISTING UTILITIES SHOWN ON THESE CONSTRUCTION PLANS IS APPROXIMATE ONLY. OTHER UTILITIES MAY EXIST AND MAY NOT BE SHOWN, OR MAY VARY FROM LOCATIONS SHOWN. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION AND SIZE OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK AND SHALL BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO VERIFY LOCATION AND SIZE OF ANY AND ALL UNDERGROUND OR OVERHEAD UTILITIES. NO GUARANTEES ARE EXPRESSED OR IMPLIED WITH RESPECT TO UTILITY LOCATIONS AND SIZES SHOWN HEREIN.
3. IN THE EVENT OF ANY DISCREPANCIES AND/OR ERRORS FOUND IN THE CONSTRUCTION PLANS, OR IF PROBLEMS ARE ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL BE REQUIRED TO NOTIFY DESIGNER BEFORE PROCEEDING WITH THE WORK. IF DESIGNER IS NOT NOTIFIED, THE CONTRACTOR SHALL ASSUME AND TAKE RESPONSIBILITY FOR THE COST OF ANY REVISION AND ANY OTHER DAMAGES OR COSTS STEMMING THEREFROM.
4. PRIOR TO BEGINNING WORK, THE CONTRACTOR SHALL VERIFY THAT ACTUAL SITE CONDITIONS (INCLUDING, BUT NOT LIMITED TO, ELEVATIONS, GRADES AND DIMENSIONS) ARE CONSISTENT WITH THE EXISTING CONDITIONS DEPICTED ON THESE CONSTRUCTION PLANS. IN THE EVENT OF ANY DISCREPANCIES AND/OR ERRORS ARE FOUND IN THE CONSTRUCTION PLANS, OR IF PROBLEMS ARE ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL TO NOTIFY THE DESIGNER AND OWNER BEFORE PROCEEDING WITH THE WORK. COMMENCEMENT OF CONSTRUCTION BY THE CONTRACTOR SHALL INDICATE THAT THE CONTRACTOR ACCEPTS THE ACTUAL SITE CONDITIONS AS MATCHING EXISTING CONDITIONS DEPICTED ON THE CONSTRUCTION PLANS.
5. PRIOR TO BEGINNING WORK, THE CONTRACTOR SHALL VERIFY ANY AND ALL DIMENSIONS, WIDTHS, HEIGHTS, SQUARE FOOTAGES, AND ANY OTHER CALCULATIONS DEPICTED ON THESE CONSTRUCTION PLANS. NO GUARANTEES ARE EXPRESSED OR IMPLIED WITH RESPECT TO SQUARE FOOTAGES REPRESENTED ON THESE CONSTRUCTION PLANS.
6. SUBSURFACE AND ENVIRONMENTAL CONDITIONS WERE NOT EXAMINED OR CONSIDERED DURING THE PREPARATION OF THESE CONSTRUCTION PLANS AND NO REPRESENTATION IS MADE CONCERNING THE EXISTENCE OF UNDERGROUND CONTAINERS, FACILITIES, WELLS, SINK HOLES, GRAVE SITES, DEBRIS OR ANY OTHER SUBSURFACE CONDITION THAT MAY AFFECT THE USE OR DEVELOPMENT OF THIS PROJECT.
7. THE DESIGNER DOES NOT GUARANTEE THE SUITABILITY OF THE SUBSURFACE CONDITIONS FOR THE WORK INDICATED. DETERMINATION OF THE SUITABILITY OF SUBSURFACE CONDITIONS FOR THE WORK INDICATED IS SOLELY THE RESPONSIBILITY OF THE OWNER AND/OR CONTRACTOR.
8. THE DESIGNER DOES NOT GUARANTEE THE WORK OF ANY CONTRACTOR OR SUBCONTRACTOR. SHALL HAVE NO AUTHORITY TO STOP WORK, SHALL HAVE NO AUTHORITY TO DIRECT WORK, SHALL NOT BE RESPONSIBLE FOR JOB SITE SAFETY, OR HAVE ANY CONTROL OVER JOB SITE SAFETY.
9. THE CONTRACTOR IS RESPONSIBLE FOR ALL DEMOLITION AND REMOVAL NECESSARY TO ACCOMPLISH THE PROPOSED IMPROVEMENTS SHOWN ON THESE CONSTRUCTION PLANS.
10. THE CONTRACTOR SHALL VERIFY THAT THERE ARE NO CONFLICTS WITH EXISTING OR PROPOSED UNDERGROUND OR OVERHEAD UTILITY LINES OR EASEMENTS.
11. THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH THE TENNESSEE UNDERGROUND UTILITY DAMAGE PREVENTION ACT (ONE-CALL) AND FOR ESTABLISHING THE EXACT VERTICAL AND HORIZONTAL LOCATION OF EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR SHALL COORDINATE ALL CONSTRUCTION WITH THE APPROPRIATE UTILITY COMPANY. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS. THE CONTRACTOR SHALL PERFORM ALL WORK IN A MANNER THAT WILL NOT CAUSE DAMAGE TO EXISTING UTILITIES THAT ARE TO REMAIN. TO THE EXTENT ANY EXISTING UTILITIES ARE DAMAGED, CONTRACTOR SHALL REPAIR ALL DAMAGE ACCORDING TO LOCAL STANDARDS AT THE CONTRACTOR'S EXPENSE. DESIGNER IS NOT RESPONSIBLE FOR ANY DAMAGES AS A RESULT OF CONTRACTOR'S FAILURE TO COORDINATE UTILITY WORK.
12. NECESSARY AND SUFFICIENT BARRICADES, LIGHTS, SIGNS, AND OTHER TRAFFIC CONTROL MEASURES AS MAY BE NECESSARY FOR THE PROTECTION AND SAFETY OF THE PUBLIC SHALL BE PROVIDED AND MAINTAINED THROUGHOUT THE CONSTRUCTION PERIOD.
13. THE CONTRACTOR SHALL ENSURE COMPLIANCE WITH ALL APPLICABLE RULES, REGULATIONS, AND CODES WITH RESPECT TO STORM WATER DISCHARGES, OR SEDIMENT OR EROSION CONTROL THROUGHOUT CONSTRUCTION. THE GRADING CONTRACTOR SHALL USE WHATEVER MEASURES ARE REQUIRED TO PREVENT SILT AND CONSTRUCTION DEBRIS FROM FLOWING ONTO ADJACENT PROPERTIES. THE CONTRACTOR SHALL COMPLY WITH ALL LOCAL EROSION, CONSERVATION AND SILTATION ORDINANCES.
14. THE ESCAPE OF EROSION AND SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO OR CONCURRENT WITH LAND DISTURBING ACTIVITIES. THE DESIGNER IS NOT RESPONSIBLE FOR ANY EROSION OR SEDIMENT PROBLEMS ENCOUNTERED DURING CONSTRUCTION.



PROJECT SUMMARY

LEGACY SOUTH BUILDERS 615.861.1669 2012 RESIDENTIAL BUILDING CODE

BEDROOMS WIDTH 25'-0"
FULL BATHS DEPTH 19'-0"
HALF BATHS HEIGHT 23'-7 1/4"

HEATED/COOLED	
LEVEL	AREA
FLOOR 2	448 SF
GRAND TOTAL: 1	448 SF

GARAGES	
LEVEL	AREA
TOP FOUNDATION	446 SF

FLOOR 2	448 SF
GRAND TOTAL: 1	448 SF

TOP FOUNDATION	446 SF
----------------	--------

SHEET LIST	
SHEET NAME	SHEET NUMBER
COVER SHEET	A0
FOUNDATION/ROOF	A1.0
FLOOR PLANS	A1.2
FRONT ELEVATION	A2.0
SIDE ELEVATIONS	A2.2

COVER SHEET	A0
FOUNDATION/ROOF	A1.0
FLOOR PLANS	A1.2
FRONT ELEVATION	A2.0
SIDE ELEVATIONS	A2.2



**1510 HOLLY ST DADU
 NASHVILLE, TN**

IT IS THE RESPONSIBILITY OF THE OWNER AND/OR CONTRACTOR TO VERIFY THAT THE PLANS MEET ANY AND ALL CODES IN THE AREA IN WHICH THE STRUCTURE WILL BE BUILT PRIOR TO CONSTRUCTION. OWNER AND/OR CONTRACTOR TO VERIFY ALL DIMENSIONS PRIOR TO BEGINNING CONSTRUCTION. ALL STRUCTURAL COMPONENTS TO BE VERIFIED BY SUPPLIER AND/OR ENGINEER PRIOR TO BEGINNING CONSTRUCTION. CONTRACTOR SHALL VERIFY SITE AND REPORT ANY CONDITIONS THAT MAY CONFLICT WITH DESIGN TO DESIGNER. CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR ANY DISCREPANCIES NOT REPORTED.


No.	Revision Description	Date
1	Initial Concept	11/4/19

COVER SHEET


DRAWING STATUS: PRELIMINARY
 DATE: 6/29/20
 DRAWN BY: J. KURKIMILIS

A0

THESE ARCHITECTURAL PLANS ARE PROTECTED BY COPYRIGHT LAW. THE REPRODUCTION OR UNAUTHORIZED USE IS STRICTLY PROHIBITED. THOSE IN VIOLATION WILL BE PURSUED TO THE FULLEST EXTENT UNDER THE LAW INCLUDING BUT NOT LIMITED TO DAMAGES AND RELATED ATTORNEY FEES.



① TOP FOUNDATION
3/8" = 1'-0"



② DADU RIDGE HEIGHT
3/8" = 1'-0"



**1510 HOLLY ST DADU
NASHVILLE, TN**

IT IS THE RESPONSIBILITY OF THE OWNER AND/OR CONTRACTOR TO VERIFY THAT THE PLANS MEET ANY AND ALL CODES IN THE AREA IN WHICH THE STRUCTURE WILL BE BUILT PRIOR TO CONSTRUCTION. OWNER AND/OR CONTRACTOR TO VERIFY ALL DIMENSIONS PRIOR TO BEGINNING CONSTRUCTION. ALL STRUCTURAL COMPONENTS TO BE VERIFIED BY SUPPLIER AND/OR ENGINEER PRIOR TO BEGINNING CONSTRUCTION. CONTRACTOR SHALL VERIFY SITE AND REPORT ANY CONDITIONS THAT MAY CONFLICT WITH DESIGN TO DESIGNER. CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR ANY DISCREPANCIES NOT REPORTED.

No.	Revision Description	Date
1	Initial Concept	11/4/19

FOUNDATION/ROOF


DRAWING STATUS: PRELIMINARY
DATE: 6/29/20
DRAWN BY: J. KURKIMILIS

AI.0


THESE ARCHITECTURAL PLANS ARE PROTECTED BY COPYRIGHT LAW. THE REPRODUCTION OR UNAUTHORIZED USE IS STRICTLY PROHIBITED. THOSE IN VIOLATION WILL BE PURSUED TO THE FULLEST EXTENT UNDER THE LAW INCLUDING BUT NOT LIMITED TO DAMAGES AND RELATED ATTORNEY FEES.

1510 HOLLY ST DADU
NASHVILLE, TN

IT IS THE RESPONSIBILITY OF THE OWNER AND/OR CONTRACTOR TO VERIFY THAT THE PLANS MEET ANY AND ALL CODES IN THE AREA IN WHICH THE STRUCTURE WILL BE BUILT PRIOR TO CONSTRUCTION. OWNER AND/OR CONTRACTOR TO VERIFY ALL DIMENSIONS PRIOR TO BEGINNING CONSTRUCTION. ALL STRUCTURAL COMPONENTS TO BE VERIFIED BY SUPPLIER AND/OR ENGINEER PRIOR TO BEGINNING CONSTRUCTION. CONTRACTOR SHALL VERIFY SITE AND REPORT ANY CONDITIONS THAT MAY CONFLICT WITH DESIGN TO DESIGNER. CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR ANY DISCREPANCIES NOT REPORTED.



① FLOOR 1
 3/8" = 1'-0"



② FLOOR 2
 3/8" = 1'-0"

DOOR SCHEDULE			
TYPE MARK	WIDTH	HEIGHT	DESCRIPTION
A	2'-8"	6'-8"	INTERIOR SINGLE FLUSH
B	2'-4"	6'-8"	INTERIOR SINGLE FLUSH
C	2'-8"	6'-8"	EXTERIOR DOOR
D	16'-0"	1'-0"	GARAGE DOOR
E	2'-7 1/32"	1'-0"	SCREEN DOOR
F	2'-4"	6'-8"	POCKET DOOR

WINDOW SCHEDULE				
TYPE MARK	WIDTH	HEIGHT	DESCRIPTION	COMMENTS
2020F	2'-0"	2'-0"	FIXED	QUAKER BRIGHTON SERIES
3050SH	3'-0"	5'-0"	SINGLE HUNG	QUAKER BRIGHTON SERIES





HEATED/COOLED	
LEVEL	AREA
FLOOR 2	448 SF
GRAND TOTAL: 1	448 SF

No.	Revision Description	Date
1	Initial Concept	11/4/19

FLOOR PLANS

DRAWING STATUS: PRELIMINARY
 DATE: 6/29/20
 DRAWN BY: J. KURKIMILIS

THESE ARCHITECTURAL PLANS ARE PROTECTED BY COPYRIGHT LAW. THE REPRODUCTION OR UNAUTHORIZED USE IS STRICTLY PROHIBITED. THOSE IN VIOLATION WILL BE PURSUED TO THE FULLEST EXTENT UNDER THE LAW INCLUDING BUT NOT LIMITED TO DAMAGES AND RELATED ATTORNEY FEES.



1510 HOLLY ST DADU
 NASHVILLE, TN


IT IS THE RESPONSIBILITY OF THE OWNER AND/OR CONTRACTOR TO VERIFY THAT THE PLANS MEET ANY AND ALL CODES IN THE AREA IN WHICH THE STRUCTURE WILL BE BUILT PRIOR TO CONSTRUCTION. OWNER AND/OR CONTRACTOR TO VERIFY ALL DIMENSIONS PRIOR TO BEGINNING CONSTRUCTION. ALL STRUCTURAL COMPONENTS TO BE VERIFIED BY SUPPLIER AND/OR ENGINEER PRIOR TO BEGINNING CONSTRUCTION. CONTRACTOR SHALL VERIFY SITE AND REPORT ANY CONDITIONS THAT MAY CONFLICT WITH DESIGN TO DESIGNER. CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR ANY DISCREPANCIES NOT REPORTED.

No.	Revision Description	Date
1	Initial Concept	11/4/19

FRONT ELEVATION

DRAWING STATUS: PRELIMINARY
 DATE: 6/29/20
 DRAWN BY: J. KURKIMILIS

THESE ARCHITECTURAL PLANS ARE PROTECTED BY COPYRIGHT LAW. THE REPRODUCTION OR UNAUTHORIZED USE IS STRICTLY PROHIBITED. THOSE IN VIOLATION WILL BE PURSUED TO THE FULLEST EXTENT UNDER THE LAW INCLUDING BUT NOT LIMITED TO DAMAGES AND RELATED ATTORNEY FEES.



**1510 HOLLY ST DADU
NASHVILLE, TN**

IT IS THE RESPONSIBILITY OF THE OWNER AND/OR CONTRACTOR TO VERIFY THAT THE PLANS MEET ANY AND ALL CODES IN THE AREA IN WHICH THE STRUCTURE WILL BE BUILT PRIOR TO CONSTRUCTION. OWNER AND/OR CONTRACTOR TO VERIFY ALL DIMENSIONS PRIOR TO BEGINNING CONSTRUCTION. ALL STRUCTURAL COMPONENTS TO BE VERIFIED BY SUPPLIER AND/OR ENGINEER PRIOR TO BEGINNING CONSTRUCTION. CONTRACTOR SHALL VERIFY SITE AND REPORT ANY CONDITIONS THAT MAY CONFLICT WITH DESIGN TO DESIGNER. CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR ANY DISCREPANCIES NOT REPORTED.

No.	Revision Description	Date
1	Initial Concept	11/4/19

SIDE ELEVATIONS

DRAWING STATUS: PRELIMINARY
 DATE: 6/29/20
 DRAWN BY: J. KURKIMILIS

Address: 1510 Holly St.

Customers: Spec

House Description: Single Home



Plan Link: https://drive.google.com/drive/folders/1qmsb31wdHFCCKTAS7jxUQ7dDcC_1gLnX

Elevation:



1510 Holly St.

Windows, Doors, Roof

Date Created	Selection	Description	Notes	Photo	Painted or Stained?
7/17/20	Window Type	Aluminum Clad	-	-	-
7/17/20	Window Grid Pattern	Plygem Mira Aluminum Clad	-		-
7/17/20	Window Exterior Color	White			
7/17/20	Shingle Roof Color	To match existing.			
7/17/20	Brick Selections	To match existing.			
7/17/20	Hardie Shingle	Hardie Plank - Lap Siding	https://www.jameshardie.com/products/hardie-plank-lap-siding		To be painted - Sherwin Williams - SW-7008 Alabaster 
7/17/20	Front Door Type	Fiberglass	https://www.jeld-wen.com/en-us/products/exterior-doors/steel/full-view-15-light	-	-
7/17/20	Front Door Selection	Steel Exterior Door: Full View 15-Light	Painted		To be painted - Sherwin Williams SW-6332 Coral Island 
7/17/20	Front Door Sill and Hinge Color	Black			
7/17/20	Back Door Type	Fiberglass	https://www.jeld-wen.com/en-us/products/exterior-doors/steel/full-view-15-light	-	-
7/17/20	Back Door Selection	Steel Exterior Door: Full View 15-Light	Painted		To be painted - Sherwin Williams SW-6332 Coral Island 
7/17/20	Gutter Color	White			

7/17/20	Front Porch Ceiling	Tounge and Grove	Painted		To be painted - Sherwin Williams - SW-7008 Alabaster 
7/17/20	Front Porch Columns	To be painted - Sherwin Williams - SW-7008 Alabaster			
7/14/20	Exterior Trim	To be painted - Sherwin Williams - SW-6332 Coral Island			

1510 Holly St.

Exterior Paint Selections

Date Created	Paint Selections:	Painted or Stained?	Selection (Color)
7/17/20	Body	Painted	SW-7008 Alabaster
7/17/20	Trim	Painted	SW-6332 Coral Island
7/17/20	Front Door	Painted	SW-6332 Coral Island
7/17/20	Back Door	Painted	SW-6332 Coral Island
7/17/20	Front Porch Ceiling	Painted	SW-7008 Alabaster
7/17/20	Back Porch Ceiling	Painted	SW-7008 Alabaster
7/17/20	Porch Columns	Painted	SW-7008 Alabaster



















GRIFFIN
WASTE SERVICES

562-4000

WHITE HOUSE
ROOFING, LLC
Insurance Claim Specialists
FREE ESTIMATE
EDDIE

