

DES Advisory Board Meeting First Quarter FY24 November 16, 2023



Agenda

- Call to Order
- 2. Review & Approval of Previous Meeting Minutes
- 3. Customer Sales
- 4. Review of DES Contractor Performance
- 5. Natural Gas Purchasing Update
- 6. FY24 Costs to Date and Budget
- 7. Marketing
- 8. Capital Projects Review & Status
- 9. Other Board Member Items
- 10. Adjourn



1. Call to Order

2. Review & Approval of Previous Meeting Minutes



3. Customer Sales

- There are 0 customers in arrears more than 30 days
- Table 3: Customer Cost Comparison for the Previous 12 Months
- Figure 3A: Historic Chilled Water Sales
- Figure 3B: Historic Steam Sales




Summary Table 3: Customer Cost Comparison for the Previous 12 Months

		Steam -	Rolling 12 Mon	nth	Chilled Water - Rolling 12 Month				
		Oct 2021- Sept 2022	Oct 2022- Sept 2023 % Dif		Oct 2021- Sept 2022	Oct 2022- Sept 2023	% Diff.		
Private	Cost	\$ 1,733,552	\$ 1,743,964	0.60%	\$ 4,497,864	\$ 4,514,174	0.36%		
	Usage (lbs or tonhrs)	93,832,584	94,819,609	1.05%	23,382,999	21,969,689	-6.04%		
State	Cost	\$ 2,182,984	\$ 2,223,241	1.84%	\$ 3,465,403	\$ 3,523,450	1.68%		
	Usage (lbs or tonhrs)	108,845,815	112,850,918	3.68%	14,053,007	13,796,320	-1.83%		
Metro	Cost	\$ 2,235,496	\$ 2,152,512	-3.71%	\$ 5,047,744	\$ 5,048,873	0.02%		
	Usage (lbs or tonhrs)	138,946,799	133,081,269	-4.22%	26,815,947	26,005,960	-3.02%		
Aggregate	Cost	\$ 6,152,032	\$ 6,119,717	-0.53%	\$13,011,011	\$13,086,497	0.58%		
	Usage (lbs or tonhrs)	341,625,198	340,751,796	-0.26%	64,251,953	61,771,969	-3.86%		
	Unit Cost	\$ 18.01	\$ 17.96	-0.3%	\$ 0.202	\$ 0.212	4.62%		




Figure 3A. Historic Chilled Water Sales



Averages include the years 2018, 2019, 2020, 2021, 2022, and 2023.



Figure 3B. Historic Steam Sales



Averages include the years 2018, 2019, 2020, 2021, 2022, and 2023.



4. Review of DES Contractor Performance

CES has made improvements in FY24 and has met several of the performance metrics for Q1. CES continues to address the system energy usage.


CES has several long-term, outstanding maintenance items in EDS tunnels that need to be addressed.

- Excellent Performance No Improvement Necessary
- Satisfactory Performance Some Improvement Could Be Made
- Poor Performance Much Improvement Necessary



Performance Measurement FY24: Steam Electric






GMQ met in all months shown.



Performance Measurement FY23: Steam Plant Eff








Performance Measurement FY23: Steam Water






GMQ exceeded in all months shown. Average difference for the quarter is > 15%.



Performance Measurement FY23: CHW Electric






GMQ met in all months shown.



Performance Measurement FY23: CHW Water





GMQ met Oct, Nov, Dec, Jan, Feb, and Mar.



FY23 FEA True-up

	CES Charged Metro and Customers Paid		FY23 Annual True-up		Annual Adjustment for Metro and Customers	
Steam Electric		15,056.19	\$	14,141.33	\$	(914.86)
Steam Fuel		(10,581.71)	\$	1,208.59	\$	11,790.30
Steam Water	\$	(6,047.22)	\$	(6,028.02)	\$	19.20
Subtotal	\$	(1,572.74)	\$	9,321.90	\$	10,894.64
Chilled Water Electric	\$	100,468.42	\$	75,819.83	\$	(24,648.59)
Chilled Water Water	\$	(8,520.96)	\$	(180.90)	\$	8,340.06
Subtotal	\$	91,947.46	\$	75,638.93	\$	(16,308.53)
Total		90,374.72	\$	84,960.83	\$	(5,413.89)



Water Treatment

Q1FY24 Q4FY23 Q3FY23 Q2FY23

- Steam and Condensate





- Corrosion
- ❖ Iron
- Hardness
- Chlorine/Sulfite
- Condensing Water
 - Conductivity
 - Biologicals
- Chilled Water
 - Hardness
 - Corrosion
 - EGF and Customer Biologicals Good
 - Deposits





















Side Stream Filter Performance



Decrease in backwash noted over the quarter. May data is pre-start-up; operational since May 9, 2023.



Side Stream Filter Performance



Copper and Iron are less than 0.04 ppm in October; Total solids below detectable limit since June.



EGF Walkthrough

Q1FY24 Q4FY23 Q3FY23 Q2FY23

- ✓ Equipment Maintenance





- ✓ Operations
- ✓ Electrical
- ✓ Housekeeping
- ✓ Building Structure
- ✓ Building Exterior and Grounds



































EDS Walkthrough

Q1FY24 Q4FY23 Q3FY23 Q2FY23

- ✓ Overall Status; Tunnels
- ✓ Overall Status; Vaults

✓ Housekeeping

- ✓ Maintenance Items
 - ✓ Piping

O- **O**- **O**-

✓ Insulation R/R

✓ Water Infiltration

<u>+</u> + + + + +

✓ Corrosion

- ✓ Lower Priority/Deferred
- _

✓ Safety Items



5. Natural Gas Purchasing

- Natural Gas Purchasing Review
 - ❖ Table 5: FY24 Gas Spending & Budget Comparison
 - Figure 5: Actual and Projected Fuel Cost Comparison




Table 5: FY24 Gas Spending & Budget Comparison

	Actual FY24 To Sept 30	Budget FY24	Percent Difference
Steam Sendout (Mlbs)	59,785	63,394	-5.7%
Fuel Use (Dth) (includes propane)	81,329	90,844	-10.4%
Plant Eff (Dth/Mlb)	1.360	1.433	-5.1%
Total Gas Cost (includes propane)	\$385,518	\$500,553	-23.0%
Unit Cost of Fuel (\$/Dth)	\$4.740	\$5.510	-14.5%

Excludes consultant fees, FEA, and pre-purchased and stored propane; Includes transportation and actual propane costs and usages. Budget values include price and weather contingencies.



Figure 5. Actual and Projected Fuel Cost Comparison



Currently hedging 70% of natural gas through FY24 and 10% through FY25; transportation costs included.



6. FY24 Costs to Date

Item	FY23 Budget		FY24 Budget		FY24 Actual		Percent of	
						to date	FY24 Budget	
FOC's	\$	4,006,800	\$	4,127,000	\$	1,031,756	25.00%	
Pass Throughs								
Administrative Costs	\$	932,100	\$	638,300	\$	166,427	26.07%	
Chemicals	\$	255,700	\$	331,200	\$	67,460	20.37%	
R&I Fund Transfers	\$	303,700	\$	312,900	\$	78,225	25.00%	
Water/Sewer	\$	773,400	\$	1,152,000	\$	487,211	42.29%	
Fuel Base	\$	2,797,256	\$	3,422,700	\$	487,645	14.25%	
Fuel Contingency	\$	677,044	\$	764,200	\$	-	0.00%	
Electricity	\$	6,394,800	\$	6,476,700	\$	2,009,825	31.03%	
ORF Deposit	\$	85,800	\$	188,200	\$	47,050	25.00%	
Debt Service	\$	4,311,300	\$	4,774,000	\$	1,720,046	36.03%	
Total Expenses	\$	20,537,900	\$	22,187,200	\$	6,095,645	27.47%	
Total Revenues	\$	20,163,600	\$	21,802,800	\$	5,599,492	25.68%	
Metro Funding	\$	374,300	\$	384,400	\$	96,100	25.67%	



7. Marketing

- Remaining Capacity for Sale (approximate)
 - 2,429 tons of chilled water
 - 35,105 pph of steam
- Potential New Customer Interest
 - ~6,000 tons
 - ~87,000 pph (or equivalent)
- East Bank Development Master Developer
 - DES met with The Fallon Company to discuss district energy opportunities on the East Bank with particular attention to their developments
 - The following information was provided by DES to show the favorability of district energy for potential developments:



Met with The Fallon Company

- Introductory discussion: Achieving Key East Bank Plan
 Considerations Utilizing District Energy
- Opportunities, benefits and approach for incorporating DES into East Bank Waterfront Initial Development Area





Advanced Technology: addressing energy efficiency standards and environmental market demands

- Thermal storage
- High efficiency chillers
- Heater/chillers
- Water/ground source heat pumps
- Condensing boilers







Design Innovation: making district energy part of a seamless infrastructure

- Innovative planning and design taking place now
- Incorporate components of District Energy into the overall master plan
- Designed with minimal impact on overall space utilization and aesthetic



Future Opportunities: addressing long-term growth demands

- Central plant is developed on the East Bank
- Future needs can be addressed by adding additional capacities and capabilities





- Peabody St Development
 - 1st and KVB
 - Potential ~1,100 tons and ~17,000 MBTUH hot water
 - Early stages of discussions
 - 4th and Lea Ave
 - Potential ~1,000 tons and no steam or hot water
 - Residential and retail
 - Re-evaluating development; on hold
 - Peabody and Rutledge
 - Potential ~2,000 tons and ~36,000 MBTUH hot water
 - Residential and retail
 - Early stages of discussions



- New Development North of KVB
 - Printer's and Banker's Alley
 - ~450 tons and no steam
 - Apartment and retail development
 - Development on hold
 - 7th and Commerce
 - 660 tons and 14,500 pph steam
 - Hotel, restaurants and retail
 - Development on hold; awaiting executed CSA
 - 8th and Demonbreun
 - 1,300 tons and no steam
 - Hotel, restaurants and retail
 - Building design progressing with DES



8. Capital Expenditure Update

	Spent to End of FY23	FY24 Spending	Balance to Date (10/23/23)
R&I Projects	\$4,644,774	\$112,647	\$269,927
49116-DES Infrastructure Fund	\$5,011,324	\$140,490	\$4,222,057
Total	\$9,656,098	\$253,134	\$4,491,984



Active Capital Projects – General & Marketing

- DES 163: Peabody Union working with developer on Guthrie St. impact to DES; blasting is complete
- DES 192: Peabody St. Developments survey of routing down Peabody; DES plan for expansion in area with new customers
- DES 195: DES Parking Area on hold pending Guthrie St. mods



Active Capital Projects – General & Marketing

- DES 201: East Bank Development ongoing development and marketing activities related to the proposed Titans stadium, Oracle, and other potential developments on the East Bank
- DES 202: 7th and Commerce Hotel awaiting executed CSA
- DES 203: Printer's and Banker's Alley Building building development on hold; intends to use DES CHW



Active Capital Projects – Corrosion Repair/Prevention

- DES 178: MH 5 Repairs corrosion/concrete/insulation repairs;
 piping insulation was completed. This project is now in close-out.
- DES 194: MH B4 Repairs cleaning and coating of structural steel; re-insulation of piping; coating and the field applied insulation was completed during the 4th Qtr FY23; the insulation blankets did not fit properly and had to be modified by the manufacturer. All but one of the blankets were received and have been installed. The last blanket is on order.
- DES 211: AA Birch Tunnel and MH D Repairs cleaning and coating of structural steel pipe and platform supports is needed. TEG is working on scope, specifications and drawings. Anticipate work to begin during the 3rd Qtr FY24.



- DES 191: MH 20 Repairs condensate return piping leaking (corrosion); ground/surface water collection/diversion needed; new access ladder needed; bid in late 3rd Qtr FY22; contractor delays; supply chain delays; all work except insulation and capping a 2" pipe is complete. Anticipate construction completion during 2nd Qtr FY24.
- DES 196: Exploratory Excav. & Cond. Leak Repair at MH 9 involves condensate return piping replacement between MH 9 and MH 10 and additional work at MH 11; project was bid during the 4th Qtr FY23, only one bid was received, and pricing was prohibitive; TEG and CES met with an alternate contractor and received pricing much less than bid pricing. Work is scheduled to begin in October 2023.
- DES 198: MH18 Condensate Pump Replacement construction began in September; commissioning expected in Q2FY24.



- DES 206: 7th Ave Tunnel Fan Replacement 7th Ave Tunnel ventilation fan disintegrated while in operation; no injuries; new fan was ordered; work began during 1st Qtr FY24. Electrical equipment had to be re-ordered due to water damage. Anticipate project completion prior to end of 2nd Qtr FY24.
- DES 207: MH N1 Insulation CES is installing most of the insulation under their Amendment 2 obligations with the balance being paid for by Metro; work scheduled to begin in October 2023 during lower humidity so piping will not be sweating during installation.
- DES 208: 2023 Steam Outage several repairs are needed in the EGF and EDS which requires a steam outage; outage took place September 24-25, 2023; awaiting re-insulation of disturbed piping. Anticipate completion during 2nd Qtr FY24.



- DES 209: MH B2 Sump Pump Discharge Repair sump pump discharge piping is either obstructed or damaged preventing evacuation of groundwater accumulation; obstruction/damage has been located using pipe tracing technology; work planned for October 2023.
- DES 210: MH C Sump Pump Installation MH C is located adjacent to MTA bus station which complicates review and pumping manhole; TEG has obtained permission from MTA to use power from bus station for an electric sump pump in MH C; TEG investigating cost with DES-196 contractor because of proximity to work site; if cost is reasonable, project will be added to DES-196 as a change order.



- DES 212: MH 2 End Can Replacement Steam piping end can assembly is corroded and requires replacement. TEG provided drawings and met with contractor to review work. Anticipate work to begin during 2nd Qtr FY24.
- DES 213: 4th, 7th & Broadway Tunnel Piping Slide Support Repairs several pipe slides are damaged due to use over past 38+ years;
 TEG is working on repair/replacement scope and drawings.
 Anticipate bidding work during the 3rd Qtr FY24.
- DES 214: Chiller 2 R'newal chiller 2 issues during quarter prompted review of machine; Trane recommended their R'newal program to replace compressors, motors, etc.; with 7-year warranty; work anticipated in Q2FY24.



Constellation Energy Solutions, LLC System Operator





9. Other Board Member Items

Election of Board Chair

Operating Management Agreement Development (current agreement expires end of FY25)



10. Adjourn

- Advisory Board Meeting Schedule
- FY24 − 2nd Quarter Meeting − February 15, 2024
- > FY24 3rd Quarter Meeting May 16, 2024
- > FY24 4th Quarter Meeting August 15, 2024
- ➤ FY24 1st Quarter Meeting November 21, 2024